

I hereby give notice of an Ordinary meeting of the:

<b>Meeting</b>	<b>Raupo Drainage Committee</b>
<b>Date</b>	Thursday 16 August 2018
<b>Venue</b>	Raupo Drainage Board Offices – Wharf Road, Ruawai
<b>Time</b>	10.00am

---

## **Open Agenda**

---

### **Membership**

Chair: Ian Beattie

Members: Councillor Anna Curnow, Greg Gent, David Hart, Brian Madsen, Ross McKinley,  
Mayor Jason Smith, Ken Whitehead

Staff and Associates:

Land Drainage Co-ordinator, Executive Assistant, Governance Advisor (Minute-taker)

## Contents

		<b>Page</b>
<b>1</b>	<b>Opening</b>	
1.1	Present	1
1.2	Apologies	1
1.3	Confirmation of Agenda	1
1.4	Conflict of Interest Declaration	1
1.5	Deputations and Presentations	1
<b>2</b>	<b>Confirmation of Minutes</b>	<b>2</b>
2.1	Raupo Drainage Committee Minutes 11 May 2017	3
<b>3</b>	<b>General</b>	<b>9</b>
3.1	Asset Management Report: August 2018	11
3.2	Financial report for the period ended 30 June 2018	15
3.3	Murphy Bower Stopbank – August 2018	19
<b>4</b>	<b>Closure</b>	<b>103</b>

**Ordinary meeting of the Raupo Drainage Committee  
Thursday 16 August 2018 in Ruawai**

**1 Opening**

**1.1 Present**

**1.2 Apologies**

**1.3 Confirmation of Agenda**

The Committee to confirm the Agenda.

**1.4 Conflict of Interest Declaration**

Committee members are reminded of the need to be vigilant to stand aside from decision-making when a conflict arises between their role as a Committee member and any private or other external interest they might have. It is also considered best practice for those members to the Executive Team attending the meeting to also signal any conflicts that they may have with an item before the Committee.

**1.5 Deputations and Presentations**

## **2 Confirmation of Minutes**

### **2.1 Raupo Drainage Committee Minutes 11 May 2018**

**General Manager Governance, Strategy and Democracy** 1603.22

#### **Recommended**

*That the unconfirmed minutes of the Raupo Drainage Committee meeting held on 11 May 2018 be confirmed as a true and correct record.*



<b>Meeting</b>	<b>Raupo Drainage Committee</b>
<b>Date</b>	Friday 11 May 2018
<b>Venue</b>	Raupo Drainage Board Offices – Wharf Road, Ruawai
<b>Time</b>	Meeting commenced at 10.00am Meeting concluded at 11.30am
<b>Status</b>	Unconfirmed

---

## **Minutes**

---

### **Membership**

Chair: Ian Beattie

Members: Councillor Anna Curnow, Greg Gent, David Hart, Brian Madsen, Ross McKinley,  
Mayor Jason Smith, Ken Whitehead

### **Staff and Associates:**

Chief Operating Officer and General Manager Infrastructure, Land Drainage Co-ordinator,  
Governance Advisor (Minute-taker)

Jason Marris

**General Manager Governance, Strategy and Democracy**

## Contents

<b>1</b>	<b>Opening.....</b>	<b>3</b>
1.1	Present.....	3
1.2	Apologies .....	3
1.3	Confirmation of Agenda .....	3
1.4	Conflict of Interest Declaration .....	3
1.5	Deputations and Presentations.....	3
<b>2</b>	<b>Confirmation of Minutes.....</b>	<b>4</b>
2.1	Raupo Drainage Committee Minutes 16 November 2017.....	4
2.2	Raupo Drainage Committee Minutes 15 February 2018 .....	4
<b>3</b>	<b>General.....</b>	<b>4</b>
3.1	Asset Management Report: February 2018.....	4
3.2	Asset Management Report: May 2018 .....	4
3.2	Raupo Financial Report – period ended 31 December 2017 .....	5
3.3	Raupo Financial Report – period ended 31 March 2018.....	5
<b>4</b>	<b>Closure.....</b>	<b>5</b>
4.1	General Business - Extension to Raupo Drainage District A.....	5

**Minutes of the meeting of the Raupo Drainage Committee****Friday 11 May 2018 in Ruawai****1 Opening****1.1 Present**

[Secretarial Note: Councillor Jonathan Larsen stepped down from this Committee, Councillor Curnow [incorrectly stated 'Councillor del la Varis-Woodcock' in the agenda] was appointed in March 2018.]

Chair: Ian Beattie

Members: Councillor Anna Curnow, Greg Gent, David Hart, Ross McKinley,  
Mayor Jason Smith and Ken Whitehead

**In Attendance**

<b>Name</b>	<b>Designation</b>	<b>Item(s)</b>
Shelley Paniora	Executive Assistant	All (Minute-taker)
Wayne Crump	Drainage Co-ordinator	All

**1.2 Apologies**

**Moved Beattie/McKinley**

*That the apology of Brian Madsen be received.*

**Carried**

**1.3 Confirmation of Agenda**

The Committee to confirm the Agenda.

**1.4 Conflict of Interest Declaration**

Nil.

**1.5 Deputations and Presentations**

Nil.

## 2 Confirmation of Minutes

### 2.1 Raupo Drainage Committee Minutes 16 November 2017

Democratic Services Manager 1603.22

**Moved Beattie/Whitehead**

*That the unconfirmed minutes of the Raupo Drainage Committee meeting held on 16 November 2017 be confirmed as a true and correct record.*

**Carried**

### 2.2 Raupo Drainage Committee Minutes 15 February 2018

Administration Manager 1603.22

**Moved Beattie/Whitehead**

*That the unconfirmed minutes of the Raupo Drainage Committee meeting held on 15 February 2018 be confirmed as a true and correct record.*

**Carried**

## 3 General

### 3.1 Asset Management Report: February 2018

Land Drainage Co-ordinator 4303.24

**Moved Beattie/Whitehead**

*That the Raupo Drainage Committee receives the Land Drainage Co-ordinator's report 'Asset Management Report: October 2017' dated 08 November 2017. This will enable the Committee to be informed of the current issues.*

**Carried**

### 3.2 Asset Management Report: May 2018

Land Drainage Co-ordinator 4303.24

**Moved Curnow/Whitehead**

*That the Raupo Drainage Committee receives the Land Drainage Co-ordinator's report 'Asset Management Report: May 2018 dated 26 April 2018. This will enable the Committee to be informed of the current issues.*

**Carried**

### 3.2 Raupo Financial Report – period ended 31 December 2017

Financial Services Manager                      4303.24

**Moved      Beattie/Whitehead**

*That the Raupo Drainage Committee receives the tabled Raupo Drainage District Financial Report – period ended 31 December 2017.*

**Carried**

### 3.3 Raupo Financial Report – period ended 31 March 2018

Financial Services Manager                      4303.24

**Moved      Hart/McKinley**

*That the Raupo Drainage Committee receives the tabled Raupo Drainage District Financial Report – year ended 31 March 2018.*

**Carried**

## 4 Closure

### 4.1 General Business - Extension to Raupo Drainage District A

Land Drainage Coordinator                      4303.24

The Board was asked to accept an additional 248 metres of drain into Raupo Drainage District A with the creation of an additional property from Peter and Sara Ball. The reason being that the new property requires a drainage outlet and does not currently have an outlet. The new drain would be numbered 6C in the network.

**Moved      Gent/Hart**

*That the Raupo Drainage District accept an additional 248 metres of drain to be maintained as part of the wider drainage network, into the Raupo Drainage District A, from Lot 1 DP 396376.*

**Carried**

The meeting closed at 11.30am.

**Confirmed** .....

**Chair** .....



### 3 General





**File number:** 4303.24 **Approved for agenda**

**Report to:** Raupo Drainage Committee

**Meeting date:** **16 August 2018**

**Subject:** **Asset Management Report: August 2018**

**Date of report:** **07 August 2018**

**From:** Wayne Crump, Land Drainage Co-ordinator

**Report purpose:**  Decision  Information

**Assessment of significance:**  Significant  Non-significant

**Summary**

This report summarises the work that has been undertaken over the last month and work that is planned or recommended in the forthcoming months. The Committee is asked to receive the report.

**Recommendation**

*That the Raupo Drainage Committee receives the Land Drainage Co-ordinator's report 'Asset Management Report: August 2018' dated 07 August 2018. This will enable the Committee to be informed of the current issues.*

**Reason for the report**

To inform the Committee of the current issues.

**Background**

The Raupo Drainage Committee meets four times each year to consider maintenance and renewal works that are required in the Raupo Drainage District. The Land Drainage Co-ordinator's report summarises the maintenance and renewal work that has been done over the period and outlines the future work programme.

**Issues****Stopbanks**

Stop bank maintenance in the past financial year of \$11,514 was made up of \$7,247 for the supply of limestone and digger works to build up over floodgates and repair access. Costs associated with survey of the stopbanks heights in these area were \$967, and the cost of purchase and installation of rail iron posts for the stopbank gates was \$3,230.

Stopbank capital works to widen and raise 230m of stopbank between Wilson Landing and Simpson Road was \$61,517. This was funded from the 2017/2018 budget and the previous year's unused budget carryover. Lands and Survey completed a survey of stopbank levels from Donovan's Bluff to the Awaroa outlet for a cost of \$3,180.

Surveys works and Geo Tech test bores were completed in sections of stopbank in the Bowers property at \$23,831.

**Floodgates**

Floodgate inspections have continued through the winter months. Debris has been removed from floodgates 45, 5, 1 and 20.

The door face timbers have been replaced on floodgate 33 (Raupo Landing). New material has been ordered to fabricate a new door and alterations to the door support points are planned.

Cross chains have been fitted to the floodgate door on No 53 (Floodgate Road). This should prevent the door from swinging side to side during certain stages of discharge.

During the weekend of 14 July 2018, weather events coincided with 3.7m high tides causing floodwater to back flow through Floodgate No 6 (Tramline/Wallace Road) into Drain No 6. This was due to the head wall leaning outwards and parting from the culvert, allowing water pushed up by the tide, to flow in the top of the culvert. This situation had been discussed at committee level with no recommendation for repair, replace or remove being resolved, and until recently, this floodgate had given no problems. A bund was placed in front of the floodgate and later removed when temporary repairs were made to the floodgate head wall and culvert area. A permanent repair to the head wall and culvert will be done in the summer months.

#### ***Machine cleaning***

Machine cleaning for the past financial year was \$20,592. This was made up of mostly weed raking required in August 2017 at a cost of \$13,607 in drains 24, 20, 19, 4, 39, 22, 6 and 26. Further weed raking was required during mid May 2018 at a cost of \$6,230. Drains cleared were:

- Drain 20 (SH12 Reynard > Dunn Road),
- Drain 19 (Williams Road > Murphy),
- Drain 24 (Tramline Crosby)
- Drain 24 and
- Part of Drain 2 (Preston)

#### ***Drain Spraying***

The 2017/2018, Contract Spraying came in at a cost of \$81,293. This included ordered works, spraying K canal (northern side) below SH12 where the long reach digger had cleaned. Further works have been completed in K canal below SH12 (southern side) at a cost of \$2,078. Bullrush spraying below Sunrise bridge G canal to the Double Creek bridge at a cost of \$1,402, and the Floodgate outlet of No 20 (Old Maori) at a cost of \$697.

#### ***Miscellaneous***

The miscellaneous expenses this last financial year are made up of fencing the Raupo yard at a cost of \$920, supply of padlocks for the stopbank gates at a cost of \$325.80, and replacement and installation of a new stove in the Raupo rental house.

### **Factors to consider**

#### ***Community views***

The community expects the Committee to have a good understanding of and to govern the land drainage requirements for the Raupo District.

#### ***Policy implications***

There are no policy implications created by this report.

**Financial implications**

There are no financial implications created by this report. All work recommended falls within the approved budget for the Raupo Drainage District.

**Legal/delegation implications**

There are no legal implications created by this report and the Committee has the delegated authority to receive the report and make recommendations as to the work required.

**Options**

**Option A:** That the Committee receives the Asset Management Report as written.

**Option B:** That the Committee declines to receive the Asset Management Report as written.

**Assessment of options**

The community expects the Committee to be informed as to the maintenance and renewal work being undertaken by Council on their behalf. Receiving the Asset Management Report is confirmation that they have been informed.

**Assessment of significance**

This report does not trigger Council's Significance and Engagement Policy.

**Recommended option**

The recommended option is Option A.



**3.1 Financial report for period ended 30 June 2018**

**Financial Services Manager**                      **4303.24**

**Recommended**

*That the Raupo Drainage Committee receives the Raupo Drainage District financial report for period ended 30 June 2018.*



**Raupo Drainage District  
Financial report for the period ended 30 June 2018**

<b>Raupo Drainage District</b>	Actual year ended 30.06.2017	Budget year ended 30.06.2018	Actual year ended 30.6.2018
Funds/Deficit from prior period	319,113	-	308,754
Rent received	9,357	7,892	8,960
Rates	340,479	342,004	348,421
<b>Funds available</b>	<b>668,949</b>	<b>349,896</b>	<b>666,135</b>
Administration Costs	23,972	4,805	6,435
Committee Costs	1,110	1,691	1,200
Maintenance Costs (note 1)	150,408	153,566	149,509
<b>Total Operating Costs</b>	<b>175,490</b>	<b>160,062</b>	<b>157,144</b>
<b>Total Capital costs (note 2)</b>	<b>184,705</b>	<b>379,699</b>	<b>278,935</b>
<b>Total Costs</b>	<b>360,194</b>	<b>709,304</b>	<b>296,234</b>
<b>Funds Passing to Future Period</b>	<b>308,754</b>	<b>- 359,408</b>	<b>369,902</b>

## Note 1

<b>Maintenance Analysis</b>	Actual year ended 30.06.2017	Budget year ended 30.06.2018	Actual year ended 30.6.2018
Floodgates	33,633	10,699	25,374
Pumps	2,010	2,200	1,200
Machine Cleaning	17,525	19,363	20,592
Spraying	83,735	75,657	81,294
Stopbanks	3,300	36,720	11,514
Miscellaneous (incl garage)	5,471	2,246	2,717
Power	1,306	2,718	3,255
Insurance	406	769	415
Rates payments	1,934	1,994	1,994
Rate remissions	1,088	1,200	1,152
<b>Total maintenance</b>	<b>150,408</b>	<b>153,566</b>	<b>149,509</b>

## Note 2

<b>Capex Analysis</b>	Actual year ended 30.06.2017	Budget year ended 30.06.2018	Actual year ended 30.6.2018
Floodgates	184,705	320,000	190,427
Pumps			
Stopbanks		59,699	64,677
Stopbanks - Murphy Bowers			23,832
<b>Total capital expenditure</b>	<b>184,705</b>	<b>379,699</b>	<b>278,935</b>



**File number:** 4303.24 **Approved for agenda**   
**Report to:** Raupo Drainage Committee  
**Meeting date:** **16 August 2018**  
**Subject:** **Murphy Bower Stopbank, August 2018**  
**Date of report:** 09 August 2018  
**From:** Donnick Mugutso, Acting General Manager Infrastructure  
**Report purpose**  **Decision**  **Information**  
**Assessment of significance**  **Significant**  **Non-significant**

### Summary

The Murphy Bower stopbank issue has been ongoing for some time. Previous reports have discussed historical issues of this stopbank, Council's legal position, a previous report from Duffill Watts and King Limited, and proposed a solution and a way forward.

Subsequent to those reports, the affected landowner has been contacted and supplied ensuing reports, discussions and options into the existing state of the stopbanks, with possible remediation. From the report that was supplied, some prices have been sought from local contractors to implement the work.

In September 2017, Council resolved to *'Delegate responsibility to the interim Chief Executive to complete any associated works for the stopbank reinstatement of Raupo Drainage District flood protection based on feedback from community consultation and expert advice; and that the works are to be funded by Raupo Drainage Targeted Rate'*.

Due to the value of the work to be completed and the possible effects of this cost, there is now a requirement to go to public consultation to gauge the view of the community that will be affected by the works to be completed and any risk associated with a lack of a lasting resolution.

### Recommendation

*That Raupo Drainage Committee:*

- 1 *Receives the Acting General Manager Infrastructure's report 'Murphy Bower Stopbank – August 2018' dated 09 August 2018; and*
- 2 *Believes it has complied with the decision-making provisions of the Local Government Act 2002 to the extent necessary in relation to this decision; and in accordance with the provision of s79 of the Act determines that it does not require further information prior to making a decision on this matter; and*
- 3 *Delegates the Chief Executive to forward all relevant information to the affected landowners for their information just prior to undergoing limited public consultation to go out to the Raupo ratepayers at the end of August 2018.*

### Reason for the recommendation

There have been some delays in getting information and prices to get the work completed, plus issues with ensuring that Council is following best practice and not negatively affecting landowners without first

considering all of the options. The above proposal is the best recommendation to complete the required project.

### **Reason for the report**

This report is for information purposes to the Raupo Drainage Committee (the Committee) to ensure that they are aware of everything that is going on, and can answer any questions that will be raised from the consultation requirements. A copy of the Opus report (Attachment 1) and the consultation letter (Attachment 2) are included in the appendices.

### **Background**

This issue reaches back to the 1970s when the original floodgate was relocated due to sedimentation of the outfall. There have been a lot of reports and recommendations regarding this issue and a resolution was almost reached in 2005 before work was stopped.

By finally reaching this resolution and the options below, this work will be completed and the land drainage stopbank protection in this location back up to an acceptable standard.

### **Issues**

The main issues with this project are:

- 1 The current bank is substandard.
- 2 If the bank is reinstated in a method that is not outlined in the proposal from Opus (report included as Attachment 1) then the Committee and subsequently the Kaipara District Council will need to be fully aware that they will be accepting any risk associated with failure.
- 3 There is an unacceptable level of risk to the Raupo community and Ruawai township.
- 4 The work to be completed is on private property and may have to be completed against the wishes of the current owners.
- 5 There will be financial implications to the Raupo ratepayers.

### **Factors to consider**

#### ***Community views***

The community would expect the Committee to manage the risks associated with the work both financial and physical and to take the right option to mitigate the risks as efficiently and cost-effectively as possible.

#### ***Policy implications***

The recommended decision will trigger Council's Significance and Engagement Policy, because it involves \$300,000 per annum or more unbudgeted expenditure.

#### ***Financial implications***

The indicative costs for the remediation are as outlined below, the financial implications of the method chosen to go forward with will be fully modelled by Council's financial team and submitted in the report to Council as outlined in the recommendations.

### ***Legal/delegation implications***

While not a legal implication there would be a legitimate expectation that public participation would be undertaken before decision-making and is best practice.

### **Options**

**Option A:** Reinstate the original stopbank as per the Opus report with an indicative cost of \$750,000. This option would reinstate the stopbank to an acceptable level with allowances for settlement over time. It is along the original alignment of the bank that was removed over time by landowners and is the cheaper of the two options.

**Option B:** Upgrade of current alignment of the stopbank, indicative cost \$1,600,000. This option would also bring the stopbank protection up to an acceptable level allowing for settlement over time. It is twice the price but will be the most palatable option to the existing landowners and will not negatively affect them at all.

### **Assessment of significance**

The risk of this project is significant, as with the current level of stopbank construction the Ruawai Township is at risk of being inundated during a significant rain event, with a catastrophic failure of the existing substandard stopbank.

### **Recommended option**

The recommended option is **Option A**.

### **Next step**

The Raupo Drainage Committee to submit a report to Council delegating the Chief Executive to forward relevant information to the affected landowner prior to a limited consultation process with the public.

### **Attachments**

- Opus Report
- Draft Consultation Letter





# Appendix A – Drawings



# KAIPARA DISTRICT COUNCIL BOWERGATE; RUAWAI STOP BANK UPGRADE

SHEET INDEX		
SHEET No.	SHEET TITLE	REVISION No.
C01	PLAN	A
C02	OPTION 1 DESIGN PLAN	A
C03	OPTION 1 TYPICAL SECTION	A
C05	CROSS SECTIONS STN. 0.0 - 718.0	A
C06	CROSS SECTIONS STN. 758.2 - 1552.7	A
C07	CROSS SECTIONS STN. 1573.4 - 1727.7	A
C10	OPTION 2 DESIGN PLAN	A
C11	OPTION 2 TYPICAL SECTION	A
C12	OPTION 2 CROSS SECTIONS STN. 57.8 - 158.1	A

## CONCEPT DESIGN

Project No: 1-13583.00

Date: FEBRUARY 2018



DRAWING IN PROGRESS

PLOTTED ON 2018-02-09 AT 11:38:51 a.m.

CONCEPT DESIGN



LEGEND	
	TOP OF BANK
	BOTTOM OF BANK
	DRAIN
	PROPERTY BOUNDARY
	HAND AUGER POSITION
	CONE PENETROMETER POSITION

COORDINATE SCHEDULE			
NORTHING	EASTING	LEVEL	DESCRIPTION
882956.58	332361.61	0.82	AH17
882877.73	332549.04	0.98	AH18
882732.04	332539.79	1.04	AH19
882848.98	332546.58	1.04	CPT 7
883430.70	330780.23	3.21	CPT 10
882510.50	332652.65	3.13	CPT1
882738.08	332319.81	3.19	CPT2
882930.13	332032.27	2.80	CPT3
883051.04	332153.97	2.29	CPT4
883132.40	332514.18	1.73	CPT5
883062.38	332565.81	2.11	CPT6
883071.55	331853.90	1.51	CPT8
883265.18	331467.91	3.17	CPT9
881201.73	333925.91	3.36	CPT11
881203.97	333935.13	3.23	CPT11 GEO

COORDINATE SCHEDULE			
NORTHING	EASTING	LEVEL	DESCRIPTION
882529.36	332643.33	2.99	AH 2
883223.82	332543.71		AH 12
882416.24	332773.79	3.15	AH1
882625.67	332537.22	2.61	AH3
882666.33	332512.35	2.26	AH4
882723.33	332350.33	3.11	AH5
882766.32	332244.16	3.05	AH6
882912.31	332042.69	2.72	AH7
882970.17	332029.42	2.63	AH8
883031.68	332123.22	2.26	AH9
883086.54	332234.27	2.14	AH10
883222.28	332480.67	1.08	AH11
883209.09	332552.78	1.94	AH13
883136.22	332527.21	1.79	AH14
883108.60	332570.19	2.00	AH15
883009.21	332562.15	1.87	AH16

**NOTES:**

- LEVELS ARE IN TERMS OF NZ VERTICAL DATUM 2016 (ORIGIN EQ22).
- COORDINATES ARE IN MET EDEN 2000 CIRCUIT.



		Project: KAIPARA DISTRICT COUNCIL BOWERGATE- RUAWAI Stop Bank Upgrade
Drawn: S. ROTYTORI Checked: C. MOULTON Date: 12/03/2018	Approved: F. RICHTER Date: 12/03/2018	Scale: 1:2000 AT A1 Sheet No: 1-13583.00 Revision: A





















Checked	Date
Design	
Drawing	
Survey	

300 mm

200

0  
50  
100  
150

1:100 @ A1  
1:200 @ A3



**DRAWING IN PROGRESS**  
PLOTTED ON 2018-02-09 AT 11:40 a.m.  
CONCEPT DESIGN

		Project: KAIPARA DISTRICT COUNCIL BOWERGATE-RIUAWAI STOP BANK UPGRADE
Issued For Pricing A	Approval (Revision Date) 2018-02-09	Sheet: OPTION ONE CROSS SECTIONS STN. 758.2 - 1552.7
Design: S. ROTAYORI Drawn: C. HOUTHWAM	Approved: F. RICHTER State: 1100/01 TA1	Project No.: 1-13583.00 Revision: A

KAIPARA DISTRICT COUNCIL BOWERGATE-RIUAWAI STOP BANK UPGRADE	



**DRAWING IN PROGRESS**  
 PLOTTED ON 2018-02-09 AT 11:40:18 a.m.  
 CONCEPT DESIGN

Project	KAIPARA DISTRICT COUNCIL BOWERGATE- RUAWAI STOP BANK UPGRADE
Sheet	OPTION TWO DESIGN PLAN
Scale	1:13583.00
Revision	A

Client	OPUS Whangarei Office 449 P.O. BOX 1700 Whangarei 0110
Author	S. PROFFER
Checked	F. RICHTER
Drawn	C. HOUTHWAM
Scale	1:2000 AT A1



Revised / Amendment	Approval	Revision Date
A	ISSUED FOR PRICING	2018-02-09



Scale	1:2000 @ A1 1:4000 @ A3
Plot Date	2018-02-09 at 11:40:18 a.m.
Plot Size	P10 (S) Plot/NCZ/111-13583.00 Bowergate Farm Investigation/Level/200 Technical/2/0 Bowergate- Ruawai/2018-02-09_C08-96g_C10



LEGEND	
	TOP OF NEW STOPBANK
	BOTTOM OF NEW STOPBANK
	EXISTING DRAIN
	HAND AUGER POSITION
	CONE PENETROMETER POSITION

Date	
Checked	
Drawn	
Survey	

Drawn	Checked	Date



TYPICAL SECTION  
SCALE: 1:50

**DRAWING IN PROGRESS**  
PLOTTED ON 2018-02-09 AT 11:40 a.m.  
CONCEPT DESIGN

		Project: KAIPARA DISTRICT COUNCIL BOWERGATE-RIUAWAI STOP BANK UPGRADE
Issued For Pricing A	Approved / Revisio Date 2018-02-09	Sheet: OPTION TWO TYPICAL SECTION
Drawn: S. ROTOYORI Checked: F. RICHTER State: 158/AT/41	Approved Date: - Approved: - State: 158/AT/41	Project No.: 1-13583.00 Revision: A

Approved / Revisio Date 2018-02-09	Project No.: 1-13583.00 Revision: A





# **Appendix B – Geotechnical Investigation**





Checked	Date
Drawn	
Survey	

LEGEND	
-----	TOP OF BANK
-----	BOTTOM OF BANK
-----	DRAIN
-----	PROPERTY BOUNDARY
↓	HAND AUGER POSITION
⊙	CONE PENETROMETER POSITION



DRAWING IN PROGRESS

PLOTTED ON 2018-02-09 AT 11:38:51 a.m.

CONCEPT DESIGN

COORDINATE SCHEDULE			
NORTHING	EASTING	LEVEL	DESCRIPTION
882956.58	332361.61	0.82	AH17
882877.73	332549.04	0.98	AH18
882732.04	332539.79	1.04	AH19
882848.98	332546.58	1.04	CPT 7
883430.70	330780.23	3.21	CPT 10
882510.50	332652.65	3.13	CPT1
882738.08	332319.81	3.19	CPT2
882930.13	332032.27	2.80	CPT3
883051.04	332153.97	2.29	CPT4
883132.40	332514.18	1.73	CPT5
883062.38	332565.81	2.11	CPT6
883071.55	331853.90	1.51	CPT8
883265.18	331467.91	3.17	CPT9
881201.73	333925.91	3.36	CPT11
881203.97	333935.13	3.23	CPT11 GEO

COORDINATE SCHEDULE			
NORTHING	EASTING	LEVEL	DESCRIPTION
882529.36	332643.33	2.99	AH 2
883223.82	332543.71		AH 12
882416.24	332773.79	3.15	AH1
882625.67	332537.22	2.61	AH3
882666.33	332512.35	2.26	AH4
882723.33	332350.33	3.11	AH5
882766.32	332244.16	3.05	AH6
882912.31	332042.69	2.72	AH7
882970.17	332029.42	2.83	AH8
883031.68	332123.22	2.26	AH9
883086.54	332234.27	2.14	AH10
883222.28	332480.67	1.08	AH11
883209.09	332552.78	1.94	AH13
883136.22	332527.21	1.79	AH14
883108.60	332570.19	2.00	AH15
883009.21	332562.15	1.87	AH16

**NOTES:**

- LEVELS ARE IN TERMS OF NZ VERTICAL DATUM 2016 (ORIGIN EQ22).
- COORDINATES ARE IN MET EDEN 2000 CIRCUIT.

1:200 @ A1  
1:400 @ A3  
0 20 40 60 80 100 120 140 160 180 200 m

Project	KAIPARA DISTRICT COUNCIL BOWERGATE- RUAWAI STOP BANK UPGRADE		
Client	KAIPARA DISTRICT COUNCIL		
Drawn	S. ROTYTORI	Checked	
Approved	F. RICHTER	Approved Date	
Scale	1:2000 AT A1	Sheet No.	C01
Project No.	1-13583.00	Revision	A

OPUS Whangarei Office  
100 Bank Street  
Whangarei 0110

KAIPARA DISTRICT  
Kaitiaki, 100 Bowergate, Whangarei 0110

Revised / Approved	Issue / Revision Date
A	ISSUED FOR PRICING
	2018-02-09

Original Sheet Size A1 (841x594) Plot Date: 2018-02-09 at 11:38:51 a.m. Plot Size: 1115x815 a.m. Path: S:\Proj\NZ\111-13583.00 Bowergate Form Investigation\Drawings\Technical\210 Drawings\DWG\A1\A1-C01-13583.00\_C01-Ang C01



TEST RIGHT • BUILD RIGHT

Geocivil Ltd  
166 Bank Street  
Whangarei  
P: 09 438 4417  
E: info@geocivil.co.nz  
M: 027 6565 226

## TEST REPORT

Lab Job No: 8368-006  
Your ref.: 8011  
Date of Issue: 19-01-2018  
Date of Re-Issue: -  
Page: 1 of 25

### Test Report.

No.W18-013

PROJECT: Bowergate Farms Geotech Investigation

CLIENT: OPUS  
125A Bank Street,  
Whangarei

ATTENTION: Stefano Rotatori

INSTRUCTIONS: Augerholes where required (not accredited)  
Hand Held Shear Vane Test

TEST METHOD: NZGS December 2005 (not accredited)  
NZGS: August 2001

SAMPLING METHOD: N/A

TEST RESULTS: As Per Laboratory Sheets attached

G. Reid

Laboratory Technician

S.Kokich

Approved Signatory



Tests indicated as not accredited are outside the scope of the laboratory's accreditation

-CPT – Aggregates – Soil – Roading-

This report shall not be reproduced except in full, without written approval of the laboratory



# AUGERHOLE LOG

**Job No.:** 8368-006      **Borehole No.:** AH01      **Sheet:** 1 of 1  
**Report No.:** W18-013      **Coordinates:**      **Date:** 10/01/18  
**Client:** OPUS Whangarei      **Location:** Ruawai      **Ground Level:** 0  
**Client Ref. No.:** PO:8011  
**Project:** Bowergate Farm

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Values	Samples
					50	100	150	200		
Sandy TOPSOIL, traces of rootlets and very weak gravels to 10mm, brown, moist, low plasticity.	OL									
Silty CLAY, traces of sand and very weak gravels up to 5mm and fibrous organics, dry-moist, greyish brown with brown streaking, moderate plasticity.	CH									131
										23
Moisture change; moist.	CH		0.5							224
										40
Silty CLAY, traces of coarse sands, traces of fibrous organics and fine rootlets, orangey brown with grey mottling, moist-wet, moderate plasticity.	CH		1.0							121
										33
Colour change; Bluish grey with orangey brown mottling.	CH									99
										37
CLAY, some silt, traces of coarse sand, minor fibrous organics, wet, dark bluish grey, moderate to high plasticity.	CH		1.5							72
										22
End of borehole - Target depth.	CH		2.0							102
										49
										45
										33
			2.5							42
										29

**Remarks**  
 Shear vane readings from 0.3-0.9m may be inaccurate due to gravels.

**Water**  
 Standing Water Level  
 Out flow  
 In flow

**Investigation Type**  
 Hand Auger  
 Test Pit

Produced with Core-GS

<b>Contractor:</b> Geocivil	<b>Rig/Plant Used:</b>	<b>Page No.:</b> 2 of 25	<b>Logged By:</b> D.O	<b>Checked By:</b> 	<b>Hole Depth:</b> 2.50 m
--------------------------------	------------------------	-----------------------------	--------------------------	------------------------	------------------------------

# AUGERHOLE LOG

<b>Job No.:</b> 8368-006	<b>Borehole No.:</b> AH02	<b>Sheet:</b> 1 of 1
<b>Report No.:</b> W18-013	<b>Coordinates:</b>	<b>Date:</b> 10/01/18
<b>Client:</b> OPUS Whangarei	<b>Location:</b> Ruawai	<b>Ground Level:</b> 0
<b>Client Ref. No.:</b> PO:8011		
<b>Project:</b> Bowergate Farm		

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Samples
					<small>Tested in accordance with NZGS Aug 2001</small>				
					50	100	150	200	Values
Sandy TOPSOIL, traces of rootlets and very weak greavel up to 10mm, brown, moist, low plasticity.	OL								
Silty CLAY, traces of rootlets, greyish brown with orangey brown mottling, moist, moderate plasticity.	CH								124
									41
			0.5						100
									14
									102
			1.0						21
									200+
									-
			1.5						113
									19
Silty CLAY, traces of coarse sand and very weak gravels up to 5mm, wet, grey with brown streaking, high plasticity, traces of fibrous organics.	CH							64	
			2.0					17	
Moisture change; Saturated.	CH			SWL 2.10m				72	
CLAY, some silt, traces of coarse sand and fibrous organics, saturated, dark bluish grey, high plasticity.	CH							7	
								47	
End of borehole - Target depth.								14	
			2.5					34 23	

Remarks	Water		Investigation Type
	<input checked="" type="checkbox"/> Standing Water Level <input type="checkbox"/> Out flow <input type="checkbox"/> In flow	<input checked="" type="checkbox"/> Hand Auger <input type="checkbox"/> Test Pit	

<b>Contractor:</b> Geocivil	<b>Rig/Plant Used:</b>	<b>Page No.:</b> 3 of 25	<b>Logged By:</b> D.O	<b>Checked By:</b> 	<b>Hole Depth:</b> 2.50 m
--------------------------------	------------------------	-----------------------------	--------------------------	------------------------	------------------------------

Produced with Core-GS

# AUGERHOLE LOG

<b>Job No.:</b> 8368-006	<b>Borehole No.:</b> AH03	<b>Sheet:</b> 1 of 1
<b>Report No.:</b> W18-013	<b>Coordinates:</b>	<b>Date:</b> 12/01/18
<b>Client:</b> OPUS Whangarei	<b>Location:</b> Ruawai	<b>Ground Level:</b> 0
<b>Client Ref. No.:</b> PO:8011		
<b>Project:</b> Bowergate Farm		

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Samples
					<small>Tested in accordance with NZGS Aug 2001</small>				
					50	100	150	200	Values
Silty TOPSOIL, traces of rootlets, brown, moist, moderate plasticity.	OH								
Clayey SILT, minor gravels up to 20mm (moderately strong), slightly weathered, traces of sand, traces of rootlets, brown mottled orange, moist, friable, low plasticity. Silty CLAY, traces of sand, brown with orange brown mottling/streaking, moist, high plasticity, traces of extremely weak gravels up to 10mm.	ML								208+
	CH		0.5						196
									50
									199
									39
				Groundwater Not Encountered					89
									27
Moisture change; wet.	CH		1.5						92
									39
									56
Silty CLAY, traces of sand, traces of fibrous organics, wet, bluish grey, high plasticity.	CH		2.0						34
									59
									22
									53
									27
End of borehole - Target depth.			2.5						

**Remarks**

**Water**

Standing Water Level  
 Out flow  
 In flow

**Investigation Type**

Hand Auger  
 Test Pit

<b>Contractor:</b> Geocivil	<b>Rig/Plant Used:</b>	<b>Page No.:</b> 4 of 25	<b>Logged By:</b> D.O	<b>Checked By:</b> 	<b>Hole Depth:</b> 2.50 m
--------------------------------	------------------------	-----------------------------	--------------------------	------------------------	------------------------------

Produced with Core-GS



**Job No.:** 8368-006      **Borehole No.:** AH04      **Sheet:** 1 of 1  
**Report No.:** W18-013  
**Client:** OPUS Whangarei      **Coordinates:** E 1,719,599.00 N 6,046,497.00      **Date:** 17/01/18  
**Client Ref. No.:** PO:8011  
**Project:** Bowergate Farm      **Location:** Ruawai      **Ground Level:** 0

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Values	Samples
					50	100	150	200		
Silty CLAY, brown mottled orange, moderate plasticity, dry, traces of organics(rootlets).	CH		0.5						69 11 200+	
Clayey SILT, light brown mottled orange, dry, low plasticity, traces of fine sand.	ML		1.0						132 11	
Silty CLAY, light grey, brown mottled orange, moist, moderate to high plasticity, traces of fine sand and extremely weak gravels to 5mm	CH		1.5						69 31	
Silty CLAY, bluish grey mottled orange, high plasticity, traces of sand and extremely weak gravel to 5mm, moist to wet.	CH		2.0						63 26	
Silty CLAY, bluish grey, high plasticity, wet, traces or extremely weak gravels to 10mm.	CH		2.5						57 29	
Moisture change; Saturated.	CH		2.0						54 26	
Colour change; dark grey	CH		2.5						43 17	
End of borehole - target depth.			2.5						40 14	

**Remarks**

**Water**

**Investigation Type**

Standing Water Level       Hand Auger  
 Out flow       Test Pit  
 In flow

**Contractor:** Geocivil      **Rig/Plant Used:**      **Page No.:** 5 of 25      **Logged By:** D.M.      **Checked By:**      **Hole Depth:** 2.50 m

Produced with Core-GS

# AUGERHOLE LOG

<b>Job No.:</b> 8368-006	<b>Borehole No.:</b> AH05	<b>Sheet:</b> 1 of 1
<b>Report No.:</b> W18-013	<b>Coordinates:</b>	<b>Date:</b> 17/01/18
<b>Client:</b> OPUS Whangarei	<b>Location:</b> Ruawai	<b>Ground Level:</b> 0
<b>Client Ref. No.:</b> PO:8011		
<b>Project:</b> Bowergate Farm		

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Values	Samples
					50	100	150	200		
Clayey SILT, brown mottled orange, dry, low plasticity.	ML	[Legend symbols]	0.5	Groundwater Not Encountered	[Vane Shear Strength bars]				89	
					[Vane Shear Strength bars]				11	
Silty CLAY, light brown mottled orange, dry to moist, moderate plasticity, minor organics (rootlets).	CH	[Legend symbols]	1.0	Groundwater Not Encountered	[Vane Shear Strength bars]				83	
					[Vane Shear Strength bars]				9	
Silty CLAY, light brown mottled orange, moist, moderate to high plasticity, minor organics (rootlets).	CH	[Legend symbols]	1.5	Groundwater Not Encountered	[Vane Shear Strength bars]				140	
					[Vane Shear Strength bars]				11	
Silty CLAY, some weak gravels up to 10mm, light brown mottled orange, moist, moderate plasticity, minor organics (rootlets).	CH	[Legend symbols]	2.0	Groundwater Not Encountered	[Vane Shear Strength bars]				155	
					[Vane Shear Strength bars]				31	
Silty CLAY, some weak gravels up to 10mm, grey mottled orange, moist, high plasticity, minor organics (rootlets).	CH	[Legend symbols]	2.5	Groundwater Not Encountered	[Vane Shear Strength bars]				117	
					[Vane Shear Strength bars]				29	
Silty CLAY, bluish grey, moist to wet, high plasticity, traces of organics (rootlets).	CH	[Legend symbols]	3.0	Groundwater Not Encountered	[Vane Shear Strength bars]				114	
					[Vane Shear Strength bars]				26	
Silty CLAY, dark bluish grey, wet, high plasticity, traces of organics (rootlets).	CH	[Legend symbols]	3.5	Groundwater Not Encountered	[Vane Shear Strength bars]				74	
					[Vane Shear Strength bars]				20	
Silty CLAY, dark bluish grey, wet, high plasticity, traces of organics (rootlets).	CH	[Legend symbols]	4.0	Groundwater Not Encountered	[Vane Shear Strength bars]				89	
					[Vane Shear Strength bars]				11	
End of borehole - Target depth			2.5		[Vane Shear Strength bars]				86	11

**Remarks**

**Water**

Standing Water Level  
 Out flow  
 In flow

**Investigation Type**

Hand Auger  
 Test Pit

<b>Contractor:</b> Geocivil	<b>Rig/Plant Used:</b>	<b>Page No.:</b> 6 of 25	<b>Logged By:</b> D.M	<b>Checked By:</b> 	<b>Hole Depth:</b> 2.50 m
--------------------------------	------------------------	-----------------------------	--------------------------	------------------------	------------------------------

Produced with Core-GS

# AUGERHOLE LOG

166 Bank Street,  
Whangarei,  
M:0276565226  
E:info@geocivil.co.nz

**Job No.:** 8368-006      **Borehole No.:** AH06      **Sheet:** 1 of 1  
**Report No.:** W18-013      **Coordinates:**      **Date:** 17/01/18  
**Client:** OPUS Whangarei      **Location:** Ruawai      **Ground Level:** 0  
**Client Ref. No.:** PO:8011  
**Project:** Bowergate Farm

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Values	Samples
					50	100	150	200		
Silty CLAY, light brown, mottled orange, dry, moderate plasticity, traces of minor organics (rootlets).	CH	[Legend symbols]	0.5	Groundwater Not Encountered	[Vane Shear Strength bars]				132	
					9					
					140					
					11					
					169					
					26					
					1.0	126				
					1.4					
					1.5	117				
					1.7	31				
Clayey SILT, light brown mottled orange, dry, low plasticity, traces of fine sand.	ML	[Legend symbols]	1.0	Groundwater Not Encountered	[Vane Shear Strength bars]				14	
					77					
Silty CLAY, light grey brown mottled orange, moist, moderate plasticity, traces of weak gravels to 10mm.	CH	[Legend symbols]	1.5	Groundwater Not Encountered	[Vane Shear Strength bars]				29	
					69					
Silty CLAY, traces of organics (rootlets), light grey brown mottled orange, moist, high plasticity, traces of weak gravels to 10mm.	CH	[Legend symbols]	2.0	Groundwater Not Encountered	[Vane Shear Strength bars]				26	
					57					
CLAY, some silt, bluish grey, wet, high plasticity, traces of extremely weak gravels up to 10mm.	CH	[Legend symbols]	2.5	Groundwater Not Encountered	[Vane Shear Strength bars]				17	
					31					
CLAY, some silt, dark bluish grey, saturated, high plasticity, traces of extremely weak gravels up to 10mm.	CH	[Legend symbols]	2.5	Groundwater Not Encountered	[Vane Shear Strength bars]				11	
					11					
End of borehole - target depth			2.5						31	11

**Remarks:** \_\_\_\_\_

**Water:**

- ▼ Standing Water Level
- ↖ Out flow
- ▽ In flow

**Investigation Type:**

- Hand Auger
- Test Pit

Produced with Core-GS

<b>Contractor:</b> Geocivil	<b>Rig/Plant Used:</b>	<b>Page No.:</b> 7 of 25	<b>Logged By:</b> D.M	<b>Checked By:</b> 	<b>Hole Depth:</b> 2.50 m
--------------------------------	------------------------	-----------------------------	--------------------------	------------------------	------------------------------



# AUGERHOLE LOG

166 Bank Street,  
Whangarei,  
M:0276565226  
E:info@geocivil.co.nz

<b>Job No.:</b> 8368-006	<b>Borehole No.:</b> AH07	<b>Sheet:</b> 1 of 1
<b>Report No.:</b> W18-013	<b>Coordinates:</b>	<b>Date:</b> 16/01/18
<b>Client:</b> OPUS Whangarei	<b>Location:</b> Ruawai	<b>Ground Level:</b> 0
<b>Client Ref. No.:</b> PO:8011		
<b>Project:</b> Bowergate Farm		

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Values	Samples
					50	100	150	200		
Silty CLAY, brown mottled orange, dry, moderate plasticity, traces of organics (rootlets).	CH	[Symbol]	0.5	[Symbol]	[Bar chart showing shear strength values]				126	
					[Bar chart showing shear strength values]				31	
					[Bar chart showing shear strength values]				93	
					[Bar chart showing shear strength values]				14	
Silty CLAY, light brown mottled orange, moist, moderate plasticity, traces of organics (rootlets).	CH	[Symbol]	1.0	[Symbol]	[Bar chart showing shear strength values]				169	
					[Bar chart showing shear strength values]				26	
Colour change; light brownish grey mottled orange.	CH	[Symbol]	1.5	[Symbol]	[Bar chart showing shear strength values]				97	
Silty CLAY, light brownish grey, moist, high plasticity, traces of minor organics (rootlets).	CH	[Symbol]	2.0	[Symbol]	[Bar chart showing shear strength values]				36	
					[Bar chart showing shear strength values]				69	
Silty CLAY, light grey mottled orange, wet, high plasticity, traces of weak gravel up to 10mm	CH	[Symbol]	2.0	[Symbol]	[Bar chart showing shear strength values]				26	
					[Bar chart showing shear strength values]				66	
Silty CLAY, dark bluish grey, high plasticity, saturated, traces of fibrous organics.	CH	[Symbol]	2.5	[Symbol]	[Bar chart showing shear strength values]				29	
					[Bar chart showing shear strength values]				57	
End of borehole - Target depth			2.5		[Bar chart showing shear strength values]				57	26

**Remarks**

**Water**

Standing Water Level  
 Out flow  
 In flow

**Investigation Type**

Hand Auger  
 Test Pit

<b>Contractor:</b> Geocivil	<b>Rig/Plant Used:</b>	<b>Page No.:</b> 8 of 25	<b>Logged By:</b> D.M	<b>Checked By:</b> 	<b>Hole Depth:</b> 2.50 m
--------------------------------	------------------------	-----------------------------	--------------------------	------------------------	------------------------------

Produced with Core-GS

# AUGERHOLE LOG

166 Bank Street,  
Whangarei,  
M:0276565226  
E:info@geocivil.co.nz

<b>Job No.:</b> 8368-006	<b>Borehole No.:</b> AH08	<b>Sheet:</b> 1 of 1
<b>Report No.:</b> W18-013	<b>Coordinates:</b>	<b>Date:</b> 16/01/18
<b>Client:</b> OPUS Whangarei	<b>Location:</b> Ruawai	<b>Ground Level:</b> 0
<b>Client Ref. No.:</b> PO:8011		
<b>Project:</b> Bowergate Farm		

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Values	Samples
					50	100	150	200		
Silty CLAY. light brown mottled orange, dry, moderate plasticity, traces of sand and organics (rootlets).	CH	[Symbol]	0.25	[Symbol]	[Bar chart showing shear strength values]				89	
					[Bar chart showing shear strength values]				14	
Colour change; brown mottled orange.	CH	[Symbol]	0.5	[Symbol]	[Bar chart showing shear strength values]				140	
					[Bar chart showing shear strength values]				14	
Silty CLAY. light brown mottled orange, moist, moderate plasticity, traces of sand and organics (rootlets).	CH	[Symbol]	0.75	[Symbol]	[Bar chart showing shear strength values]				74	
					[Bar chart showing shear strength values]				11	
Silty CLAY. light brown mottled orange, moist, moderate plasticity, traces of sand and organics (rootlets).	CH	[Symbol]	1.0	[Symbol]	[Bar chart showing shear strength values]				69	
					[Bar chart showing shear strength values]				14	
Silty CLAY. light brown mottled orange, moist, moderate to high plasticity, traces of sand and organics (rootlets).	CH	[Symbol]	1.25	[Symbol]	[Bar chart showing shear strength values]				89	
					[Bar chart showing shear strength values]				31	
Silty CLAY. light brownish grey mottled orange, moist to wet, high plasticity, traces of sand and organics (rootlets).	CH	[Symbol]	1.5	[Symbol]	[Bar chart showing shear strength values]				60	
					[Bar chart showing shear strength values]				29	
Silty CLAY, light brownish grey mottled orange, moist to wet, high plasticity, traces of sand and organics (rootlets).	CH	[Symbol]	1.75	[Symbol]	[Bar chart showing shear strength values]				69	
					[Bar chart showing shear strength values]				29	
Silty CLAY, bluish grey mottled orange, wet, high plasticity, traces of fibrous organics.	CH	[Symbol]	2.0	[Symbol]	[Bar chart showing shear strength values]				74	
					[Bar chart showing shear strength values]				26	
Colour change; dark bluish grey.	CH	[Symbol]	2.25	[Symbol]	[Bar chart showing shear strength values]				54	
					[Bar chart showing shear strength values]				17	
Silty CLAY, dark bluish grey mottled orange, saturated, high plasticity, traces of fibrous organics, minor weak gravel to 5mm.	CH	[Symbol]	2.375	[Symbol]	[Bar chart showing shear strength values]					
					[Bar chart showing shear strength values]					
End of borehole - target depth			2.5	[Symbol]	[Bar chart showing shear strength values]					
					[Bar chart showing shear strength values]					

**Remarks**

**Water**

Standing Water Level  
 Out flow  
 In flow

**Investigation Type**

Hand Auger  
 Test Pit

<b>Contractor:</b> Geocivil	<b>Rig/Plant Used:</b>	<b>Page No.:</b> 9 of 25	<b>Logged By:</b> D.M	<b>Checked By:</b> 	<b>Hole Depth:</b> 2.50 m
--------------------------------	------------------------	-----------------------------	--------------------------	------------------------	------------------------------

Produced with Core-GS

<b>Job No.:</b> 8368-006	<b>Borehole No.:</b> AH09	<b>Sheet:</b> 1 of 1
<b>Report No.:</b> W18-013	<b>Coordinates:</b>	<b>Date:</b> 16/01/18
<b>Client:</b> OPUS Whangarei	<b>Location:</b> Ruawai	<b>Ground Level:</b> 0
<b>Client Ref. No.:</b> PO:8011		
<b>Project:</b> Bowergate Farm		

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Values	Samples
					50	100	150	200		
Silty CLAY, light brown mottled orange, moderate plasticity, dry, traces of organics (rootlets).	CH		0.5						106	17
									100	
									129	
									17	
Silty CLAY, light brown mottled orange, moderate plasticity, moist, traces of fine sand and gravel up to 3mm.	CH		1.0						74	21
Colour change; brown mottled orange.									26	
Silty CLAY, light brown mottled orange, moderate plasticity, moist, traces of fine sand and gravel up to 3mm, traces of fibrous organics.	CH		1.5						60	26
									54	
Silty CLAY, traces of extremely weak gravels up to 5mm, wet, moderate to high plasticity, light grey brown mottled orange.	CH		2.0						52	17
Silty CLAY, bluish grey, high plasticity, moist to wet.									14	
Silty CLAY, dark bluish grey, wet, high plasticity, traces of fibrous organics.	CH		2.5						43	11
Moisture change; Saturated.									31	
Colour change; dark grey.	CH		2.5						11	11
End of borehole - Target depth									11	

<b>Remarks</b>	<b>Water</b>	<b>Investigation Type</b>
	Standing Water Level Out flow In flow	<input checked="" type="checkbox"/> Hand Auger <input type="checkbox"/> Test Pit

<b>Contractor:</b> Geocivil	<b>Rig/Plant Used:</b>	<b>Page No.:</b> 10 of 25	<b>Logged By:</b> D.M	<b>Checked By:</b> 	<b>Hole Depth:</b> 2.50 m
--------------------------------	------------------------	------------------------------	--------------------------	------------------------	------------------------------

Produced with Core-GS



# AUGERHOLE LOG

<b>Job No.:</b> 8368-006	<b>Borehole No.:</b> AH10	<b>Sheet:</b> 1 of 1
<b>Report No.:</b> W18-013	<b>Coordinates:</b>	<b>Date:</b> 16/01/18
<b>Client:</b> OPUS Whangarei	<b>Location:</b> Ruawai	<b>Ground Level:</b> 0
<b>Client Ref. No.:</b> PO:8011		
<b>Project:</b> Bowergate Farm		

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Values	Samples
					50	100	150	200		
Silty CLAY, light brown mottled orange, dry, low plasticity, traces of organics (rootlets).	CH	[Symbol]	0.2						166	
			0.3						16	
Silty CLAY, light brown mottled orange, moist, moderate plasticity, traces of organics (rootlets).	CH	[Symbol]	0.5						57	
			0.6						9	
			0.7						79	
Silty CLAY, brown mottled orange, moist, moderate to high plasticity, traces of weak gravels up to 5mm, traces of fibrous organics.	CH	[Symbol]	1.0						29	
			1.1						49	
Silty CLAY, light brown mottled orange, moist, minor black nodules (3.5mm), traces of weak gravel and fibrous organics.	CH	[Symbol]	1.3						17	
			1.4						43	
Silty CLAY, grey mottled orange, moist to wet, moist, minor black nodules (3.5mm), traces of weak gravel and fibrous organics.	CH	[Symbol]	1.5						11	
			1.6						29	
Silty CLAY, bluish grey, wet, high plasticity, traces of organics (rootlets).	CH	[Symbol]	1.8						9	
			1.9						17	
			2.0						6	
Moisture change; Saturated.	CH	[Symbol]	2.1						14	
			2.2						6	
			2.3						14	
			2.4						6	
End of borehole - Target depth			2.5						11	
									3	

**Remarks**

**Water**

Standing Water Level  
 Out flow  
 In flow

**Investigation Type**

Hand Auger  
 Test Pit

<b>Contractor:</b> Geocivil	<b>Rig/Plant Used:</b>	<b>Page No.:</b> 11 of 25	<b>Logged By:</b> D.M	<b>Checked By:</b> 	<b>Hole Depth:</b> 2.50 m
--------------------------------	------------------------	------------------------------	--------------------------	------------------------	------------------------------

# AUGERHOLE LOG

166 Bank Street,  
Whangarei,  
M:0276565226  
E:info@geocivil.co.nz

<b>Job No.:</b> 8368-006	<b>Borehole No.:</b> AH11	<b>Sheet:</b> 1 of 1
<b>Report No.:</b> W18-013	<b>Coordinates:</b>	<b>Date:</b> 11/01/18
<b>Client:</b> OPUS Whangarei	<b>Location:</b> Ruawai	<b>Ground Level:</b> 0
<b>Client Ref. No.:</b> PO:8011		
<b>Project:</b> Bowergate Farm		

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Values	Samples
					50	100	150	200		
Silty TOPSOIL, traces of sand and organics(rootlets), moist, dark brown, moderate plasticity.	OH	TS	0.0 - 0.2							
Silty CLAY, traces of sand and extremely weak gravels up to 10mm, moist, brown with orangey brown and grey streaking/mottling, moderate plasticity.	CH	TS	0.2 - 0.4						133	
			0.4 - 0.5						13	
Silty CLAY, traces of sand and very weak gravels up to 5mm, moist, grey with brown mottling, moderate plasticity, traces of fibrous organics.	CH	TS	0.5 - 0.7						104	
			0.7 - 0.8						14	
Moisture change; wet.	CH	TS	0.8 - 1.0						79	
			1.0 - 1.2						14	
Moisture change; saturated.	CH	TS	1.2 - 1.4						87	
			1.4 - 1.5						27	
Moisture change; wet.	CH	TS	1.5 - 1.7						123	
			1.7 - 1.8						29	
Moisture change; saturated.	CH	TS	1.8 - 2.0						86	
			2.0 - 2.1						26	
End of borehole - Target depth	CH	TS	2.1 - 2.2						49	
			2.2 - 2.3						21	
End of borehole - Target depth	CH	TS	2.3 - 2.4						40	
			2.4 - 2.5						14	
End of borehole - Target depth			2.5						31	
									11	

**Remarks**

**Water**

Standing Water Level  
 Out flow  
 In flow

**Investigation Type**

Hand Auger  
 Test Pit

<b>Contractor:</b> Geocivil	<b>Rig/Plant Used:</b>	<b>Page No.:</b> 12 of 25	<b>Logged By:</b> D.O	<b>Checked By:</b> 	<b>Hole Depth:</b> 2.50 m
--------------------------------	------------------------	------------------------------	--------------------------	------------------------	------------------------------

Produced with Core-GS

# AUGERHOLE LOG

<b>Job No.:</b> 8368-006	<b>Borehole No.:</b> AH12	<b>Sheet:</b> 1 of 1
<b>Report No.:</b> W18-013	<b>Coordinates:</b>	<b>Date:</b> 11/01/18
<b>Client:</b> OPUS Whangarei	<b>Location:</b> Ruawai	<b>Ground Level:</b> 0
<b>Client Ref. No.:</b> PO:8011		
<b>Project:</b> Bowergate Farm		

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Samples
					<small>Tested in accordance with NZGS Aug 2001</small>				
					50	100	150	200	Values
Silty TOPSOIL, traces of sand and organics (rootlets), dark brown, moist, moderate plasticity.	OH								
Silty CLAY, traces of sand and very weak gravels up to 5mm, moist, brown with grey and orangey brown mottling, moderate plasticity, traces of organics (bark and rootlets).	CH		0.5	Groundwater Not Encountered					100
									14
Silty CLAY, traces of extremely weak gravels up to 10mm, grey with orangey brown mottling, moist, moderate plasticity, traces of rootlets.	CH		1.0	Groundwater Not Encountered					183
									36
Silty CLAY, traces of sands and organics (rootlets), moist, brownish grey with orangey brown mottling, high plasticity.	CH		1.5	Groundwater Not Encountered					137
									17
Moisture change; wet.	CH		2.0	Groundwater Not Encountered					162
									41
End of borehole - target depth	CH		2.5	Groundwater Not Encountered					149
									59
									92
									36
									73
									12
									59
									23

**Remarks**

**Water**

Standing Water Level  
 Out flow  
 In flow

**Investigation Type**

Hand Auger  
 Test Pit

<b>Contractor:</b> Geocivil	<b>Rig/Plant Used:</b>	<b>Page No.:</b> 13 of 25	<b>Logged By:</b> D.O	<b>Checked By:</b> 	<b>Hole Depth:</b> 2.50 m
--------------------------------	------------------------	------------------------------	--------------------------	------------------------	------------------------------

Produced with Core-GS





# AUGERHOLE LOG

166 Bank Street,  
Whangarei,  
M:0276565226  
E:info@geocivil.co.nz

**Job No.:** 8368-006      **Borehole No.:** AH13      **Sheet:** 1 of 1  
**Report No.:** W18-013      **Coordinates:**      **Date:** 11/01/18  
**Client:** OPUS Whangarei      **Location:** Ruawai      **Ground Level:** 0  
**Client Ref. No.:** PO:8011  
**Project:** Bowergate Farm

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Samples
					Tested in accordance with NZGS Aug 2001				
					50	100	150	200	Values
Silty TOPSOIL, minor organics (rootlets), dark brown, moist, high plasticity.	CH								104
Silty CLAY, traces of sands and extremely weak gravels up to 5mm, brownish grey with orangey brown streaking, moist, moderate to high plasticity.	CH		0.5						29
									114
									36
									107
									34
			1.0					93	
Moisture change; wet.	CH							31	
Moisture change; Saturated.	CH							29	
	CH			SWL 1.50m				6	
	CH							29	
	CH							3	
	CH							31	
Silty CLAY, traces of sand, traces of fibrous organics, bluish grey, saturated, high plasticity.	CH		2.0					7	
Silty CLAY, traces of sands and extremely weak gravels up to 10mm and fibrous organics, dark bluish grey, saturated, high plasticity.	CH							29	
	CH							6	
End of borehole - Target depth.			2.5					24	
								1	

**Remarks** \_\_\_\_\_

**Water**  
 ▼ Standing Water Level  
 ↖ Out flow  
 ↗ In flow

**Investigation Type**  
 Hand Auger  
 Test Pit

**Contractor:** Geocivil      **Rig/Plant Used:**      **Page No.:** 14 of 25      **Logged By:** D.O.      **Checked By:**      **Hole Depth:** 2.50 m

Produced with Core-GS

# AUGERHOLE LOG

<b>Job No.:</b> 8368-006	<b>Borehole No.:</b> AH14	<b>Sheet:</b> 1 of 1
<b>Report No.:</b> W18-013	<b>Coordinates:</b>	<b>Date:</b> 16/01/18
<b>Client:</b> OPUS Whangarei	<b>Location:</b> Ruawai	<b>Ground Level:</b> 0
<b>Client Ref. No.:</b> PO:8011		
<b>Project:</b> Bowergate Farm		

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Values	Samples
					50	100	150	200		
Silty CLAY, light brown mottled orange, dry, moderate plasticity, some organic rootlets.	CH		0.49						49	
			0.51						16	
Silty CLAY, light brown mottled orange, moist, moderate to high plasticity, some organic rootlets.	CH		0.74						112	
			0.76						23	
Colour change; light brown grey mottled orange.	CH		0.91						74	
			0.93						26	
Silty CLAY, light brown mottled orange, moist, moderate to high plasticity, some organic rootlets.	CH		1.09						43	
			1.11						9	
Silty CLAY, light brown mottled orange, moist, high plasticity, some organic rootlets.	CH		1.36						69	
			1.38						11	
Silty CLAY, light brown mottled orange, moist, high plasticity, some organic rootlets.	CH		1.57						57	
			1.59						14	
Silty CLAY, bluish grey, high plasticity, moist to wet, traces of fine sand, fibrous organics, some black nodules(2.5mm).	CH		1.80	SWL 1.80m					31	
			1.82						11	
Silty CLAY, dark grey, high plasticity, saturated, traces of fine sand, fibrous organics, some black nodules(2.5mm).	CH		2.34						34	
			2.36						14	
End of borehole - Target depth			2.51						31	
			2.53						11	

<b>Remarks</b>	<b>Water</b>		<b>Investigation Type</b>	
		Standing Water Level	<input checked="" type="checkbox"/>	Hand Auger
		Out flow	<input type="checkbox"/>	Test Pit
		In flow		

<b>Contractor:</b> Geocivil	<b>Rig/Plant Used:</b>	<b>Page No.:</b> 15 of 25	<b>Logged By:</b> D.M	<b>Checked By:</b> 	<b>Hole Depth:</b> 2.50 m
--------------------------------	------------------------	------------------------------	--------------------------	------------------------	------------------------------

Produced with Core-GS



# AUGERHOLE LOG

<b>Job No.:</b> 8368-006	<b>Borehole No.:</b> AH15	<b>Sheet:</b> 1 of 1
<b>Report No.:</b> W18-013	<b>Coordinates:</b>	<b>Date:</b> 10/01/18
<b>Client:</b> OPUS Whangarei	<b>Location:</b> Ruawai	<b>Ground Level:</b> 0
<b>Client Ref. No.:</b> PO:8011		
<b>Project:</b> Bowergate Farm		

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Values	Samples
					50	100	150	200		
Silty CLAY, traces of sands and very weak gravels up to 5mm, dry to moist, light brown, moderate plasticity.	CH								200+	
Silty CLAY, some sand, traces of very weak gravels up to 5mm, light brown with brown and brownish grey streaking, moist, moderate plasticity.	CH		0.5						92	
Silty CLAY, minor sand, traces of very weak gravels up to 10mm, traces of fibrous organics, moist, brown with brownish grey and reddish brown streaking/mottling, moderate plasticity.	CH		1.0						156	
Moisture change; Wet.	CH								64	
Silty CLAY, traces of extremely weak gravels up to 10mm, light brown with brown streaking, wet, high plasticity.	CH								80	
Moisture change; Saturated.	CH								46	
CLAY, some silt, traces of fibrous organics, bluish grey, saturated, high plasticity.	CH								70	
End of borehole - target depth			2.5						36	
									86	
									54	
									26	
									13	
									24	
									11	

**Remarks**

**Water**

- Standing Water Level
- Out flow
- In flow

**Investigation Type**

- Hand Auger
- Test Pit

<b>Contractor:</b> Geocivil	<b>Rig/Plant Used:</b>	<b>Page No.:</b> 16 of 25	<b>Logged By:</b> D.O	<b>Checked By:</b>	<b>Hole Depth:</b> 2.50 m
-----------------------------	------------------------	---------------------------	-----------------------	--------------------	---------------------------

Produced with Core-GS

# AUGERHOLE LOG

166 Bank Street,  
Whangarei,  
M:0276565226  
E:info@geocivil.co.nz

<b>Job No.:</b> 8368-006	<b>Borehole No.:</b> AH16	<b>Sheet:</b> 1 of 1
<b>Report No.:</b> W18-013	<b>Coordinates:</b>	<b>Date:</b> 10/01/18
<b>Client:</b> OPUS Whangarei	<b>Location:</b> Ruawai	<b>Ground Level:</b> 0
<b>Client Ref. No.:</b> PO:8011		
<b>Project:</b> Bowergate Farm		

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Samples
					<small>Tested in accordance with NZGS Aug 2001</small>				
					50	100	150	200	Values
Silty CLAY, traces of sands and very weak gravels up to 5mm, dry to moist, light brown, moderate plasticity.	CH								
Silty CLAY, some sand, traces of very weak gravels to 5mm, light brown with brown and brownish grey streaking, moderate plasticity.	CH								104
									33
			0.5						
Silty CLAY, minor sand, traces of very weak gravels up to 10mm, traces of fibrous organics, moist, brown with brownish grey and reddish brown streaking/mottling, moderate plasticity.									122
									40
									127
									35
			1.0						
	CH								142
									47
									121
									50
									67
Silty CLAY, traces of extremely weak gravels up to 10mm, light brown with brown streaking, wet, high plasticity.	CH								30
									39
									23
CLAY some silt, traces of fibrous organics, bluish grey, saturated, high plasticity.	CH			SWL 2.20m					33
									15
End of borehole - target depth			2.5						32
									17

**Remarks**  
Shear vane readings from 0.9-1.8m may be inaccurate due to gravels.

**Water**  
 Standing Water Level  
 Out flow  
 In flow

**Investigation Type**  
 Hand Auger  
 Test Pit

Produced with Core-GS

# AUGERHOLE LOG

**Job No.:** 8368-006  
**Report No.:** W18-013  
**Client:** OPUS Whangarei  
**Client Ref. No.:** PO:8011  
**Project:** Bowergate Farm

**Borehole No.:** AH17  
**Coordinates:**  
**Location:** Ruawai

**Sheet:** 1 of 1  
**Date:** 10/01/18  
**Ground Level:** 0

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Values	Samples	
					50	100	150	200			
Silty CLAY, traces of sands and weaks gravels up to 10mm, moist, dark brown, moderate plasticity.	CH									112	43
Colour change; brownish grey with brown streaking.	CH		0.5							53	21
Moisture change; wet.	CH									29	14
Moisture change; Saturated.	CH		1.0	SWL 1.00m						14	3
CLAY, traces of sands, saturated, bluish grey, high plasticity.	CH									14	7
End of borehole - Hole collapsed			2.0							10	1

Remarks	<b>Water</b>		<b>Investigation Type</b>	
		Standing Water Level	<input checked="" type="checkbox"/>	Hand Auger
		Out flow	<input type="checkbox"/>	Test Pit
		In flow		

<b>Contractor:</b> Geocivil	<b>Rig/Plant Used:</b>	<b>Page No.:</b> 18 of 25	<b>Logged By:</b> D.O	<b>Checked By:</b> 	<b>Hole Depth:</b> 1.80 m
--------------------------------	------------------------	------------------------------	--------------------------	------------------------	------------------------------

Produced with Core-GS



# AUGERHOLE LOG

166 Bank Street,  
Whangarei,  
M:0276565226  
E:info@geocivil.co.nz

<b>Job No.:</b> 8368-006	<b>Borehole No.:</b> AH18	<b>Sheet:</b> 1 of 1
<b>Report No.:</b> W18-013	<b>Coordinates:</b>	<b>Date:</b> 10/01/18
<b>Client:</b> OPUS Whangarei	<b>Location:</b> Ruawai	<b>Ground Level:</b> 0
<b>Client Ref. No.:</b> PO:8011		
<b>Project:</b> Bowergate Farm		

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Values	Samples
					50	100	150	200		
Silty CLAY, traces of extremely weak gravels up to 10mm and rootlets, light brown, dry, moderate plasticity.	CH									
Silty CLAY, traces of coarse sands, traces of rootlets, moist, brown with greyish brown streaking/mottling, moderate plasticity.	CH		0.5						73	
									49	
									74	
									40	
Colour and moisture change; greyish brown with brown streaking and bluish grey mottling, wet.	CH								59	
									31	
Moisture change; Saturated.	CH		1.0	SWL 1.00m					14	
									3	
CLAY, some silt, traces of sands and fibrous organics, saturated, dark bluish grey, high plasticity.	CH								13	
									3	
End of borehole - Hole collapsed			1.5							
			2.0							

**Remarks**

**Water**  
 Standing Water Level  
 Out flow  
 In flow

**Investigation Type**  
 Hand Auger  
 Test Pit

<b>Contractor:</b> Geocivil	<b>Rig/Plant Used:</b>	<b>Page No.:</b> 19 of 25	<b>Logged By:</b> D.O	<b>Checked By:</b> 	<b>Hole Depth:</b> 1.50 m
--------------------------------	------------------------	------------------------------	--------------------------	------------------------	------------------------------

Produced with Core-GS

# AUGERHOLE LOG

<b>Job No.:</b> 8368-006	<b>Borehole No.:</b> AH19	<b>Sheet:</b> 1 of 1
<b>Report No.:</b> W18-013	<b>Coordinates:</b>	<b>Date:</b> 10/01/18
<b>Client:</b> OPUS Whangarei	<b>Location:</b> Ruawai	<b>Ground Level:</b> 0
<b>Client Ref. No.:</b> PO:8011		
<b>Project:</b> Bowergate Farm		

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Values	Samples
					50	100	150	200		
Silty CLAY, traces of extremely weak gravels up to 10mm and rootlets, light brown, dry, moderate plasticity.	CH									
Silty CLAY, traces of coarse sands, traces of fibrous organics and rootlets, moist, brown with greyish brown streaking/mottling, moderate plasticity.	CH		0.5						50	
Colour change; greyish brown with yellow brown and bluish grey mottling, brown streaking.	CH								17	
Moisture change; Wet.	CH								57	
Moisture change; Saturated.	CH		1.0	SWL 1.00m					26	
CLAY, some silt, traces of sands and fibrous organics, saturated, dark bluish grey, high plasticity.	CH								43	
End of borehole - Hole collapsed	CH		1.5						21	
									43	
									9	
									16	
			2.0						4	

**Remarks**

**Water**

**Investigation Type**

- Standing Water Level
- Out flow
- In flow

- Hand Auger
- Test Pit

<b>Contractor:</b> Geocivil	<b>Rig/Plant Used:</b>	<b>Page No.:</b> 20 of 25	<b>Logged By:</b> D.O	<b>Checked By:</b> 	<b>Hole Depth:</b> 1.50 m
--------------------------------	------------------------	------------------------------	--------------------------	------------------------	------------------------------

# AUGERHOLE LOG

<b>Job No.:</b> 8368-006	<b>Borehole No.:</b> AH20	<b>Sheet:</b> 1 of 1
<b>Report No.:</b> W18-013	<b>Coordinates:</b>	<b>Date:</b> 11/01/18
<b>Client:</b> OPUS Whangarei	<b>Location:</b> Ruawai	<b>Ground Level:</b> 0
<b>Client Ref. No.:</b> PO:8011		
<b>Project:</b> Bowergate Farm		

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Values	Samples
					50	100	150	200		
Clayey TOPSOIL, traces of organics(rootlets), dark brown, moist, high plasticity.	OH									
Silty CLAY, traces of extremely weak gravels to 10mm, brown with orangey brown and grey mottling, moist, moderate plasticity, traces of fibrous organics.	CH		0.5						57	
									29	
Silty CLAY, traces of sands, brownish grey with orangey brown streaking, moist, high plasticity.	CH		1.0						72	
									14	
Moisture change; Wet.	CH		1.5						92	
									27	
Moisture change; Saturated.	CH		2.0						82	
									26	
End of borehole - Target depth	CH		2.5						57	
									14	

<b>Remarks</b>	<b>Water</b>	<b>Investigation Type</b>
	Standing Water Level Out flow In flow	<input checked="" type="checkbox"/> Hand Auger <input type="checkbox"/> Test Pit

<b>Contractor:</b> Geocivil	<b>Rig/Plant Used:</b>	<b>Page No.:</b> 21 of 25	<b>Logged By:</b> D.O	<b>Checked By:</b> 	<b>Hole Depth:</b> 2.50 m
--------------------------------	------------------------	------------------------------	--------------------------	------------------------	------------------------------

Produced with Core-GS



# AUGERHOLE LOG

**Job No.:** 8368-006      **Borehole No.:** AH21      **Sheet:** 1 of 1  
**Report No.:** W18-013      **Coordinates:**      **Date:** 11/01/18  
**Client:** OPUS Whangarei      **Location:** Ruawai      **Ground Level:** 0  
**Client Ref. No.:** PO:8011  
**Project:** Bowergate Farm

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Values	Samples
					50	100	150	200		
Silty CLAY, traces of rootlets, traces of sand and weak gravels up to 5mm, dark brown with brown mottling, moist, moderate plasticity.	CH	[Symbol]	0.5	Groundwater Not Encountered	[Bar chart showing shear strength values]				126	
									14	
Colour change; dark greyish brown with orangey brown and dark grey streaking/mottling.	CH	[Symbol]	1.0	Groundwater Not Encountered	[Bar chart showing shear strength values]				200+	
Silty CLAY, minor sands, traces of very weak gravels up to 10mm, moist, greyish brown with orangey brown and light brown mottling, moderate plasticity.	CH	[Symbol]	1.5	Groundwater Not Encountered	[Bar chart showing shear strength values]				170	
									26	
Silty CLAY, traces of coarse sand, wet, brown grey with orange brown mottling, high plasticity.	CH	[Symbol]	2.0	Groundwater Not Encountered	[Bar chart showing shear strength values]				200+	
Silty CLAY, minor fibrous organics, traces of sand, grey with brown streaking, wet, high plasticity.	CH	[Symbol]	2.5	Groundwater Not Encountered	[Bar chart showing shear strength values]				157	
									26	
Silty CLAY, traces of fibrous organics, wet, dark bluish grey, high plasticity.	CH	[Symbol]	3.0	Groundwater Not Encountered	[Bar chart showing shear strength values]				117	
									80	
Moisture change; Saturated.	CH	[Symbol]	3.5	Groundwater Not Encountered	[Bar chart showing shear strength values]				21	
									11	
End of borehole - target depth	CH	[Symbol]	4.0	Groundwater Not Encountered	[Bar chart showing shear strength values]				26	
									7	

**Remarks** \_\_\_\_\_

**Water**  
 ▼ Standing Water Level  
 ◀ Out flow  
 ▷ In flow

**Investigation Type**  
 Hand Auger  
 Test Pit

Produced with Core-GS

<b>Contractor:</b> Geocivil	<b>Rig/Plant Used:</b>	<b>Page No.:</b> 22 of 25	<b>Logged By:</b> D.O	<b>Checked By:</b> 	<b>Hole Depth:</b> 2.50 m
--------------------------------	------------------------	------------------------------	--------------------------	------------------------	------------------------------

# AUGERHOLE LOG

166 Bank Street,  
Whangarei,  
M:0276565226  
E:info@geocivil.co.nz

**Job No.:** 8368-006      **Borehole No.:** AH22      **Sheet:** 1 of 1  
**Report No.:** W18-013      **Coordinates:**      **Date:** 12/01/18  
**Client:** OPUS Whangarei      **Location:** Ruawai      **Ground Level:** 0  
**Client Ref. No.:** PO:8011  
**Project:** Bowergate Farm

Geological Interpretation <small>In accordance with NZGS 2005</small>	UCS	Legend	Depth (m)	Water	Vane Shear Strength (kPa)				Values	Samples
					50	100	150	200		
Clayey TOPSOIL, traces of sands and rootlets, dark brown, moist, moderate plasticity.	OH									
Silty CLAY, some sand, traces of rootlets, dark brown with brown mottling, moist, moderate plasticity.	CH		0.5						114	
									30	
Clayey SILT, traces of sands and extremely weak gravels up to 5mm, light brown with brown streaking, dry-moist, friable, low plasticity.	ML		1.0						172	
									33	
Silty SAND, minor clay, sand is; well graded, traces of extremely weak gravels to 5mm, light brown, moist, dilatant, friable.	SM		1.5	Groundwater Not Encountered					126	
									13	
Silty CLAY, some sand, wet, grey with light grey and brown streaking, moderate plasticity.	CH		2.0						117	
									43	
Silty CLAY, traces of fibrous organics, brownish grey with bluish grey streaking, wet, high plasticity.	CH		2.5						116	
									52	
End of borehole - target depth			2.5							

**Remarks** \_\_\_\_\_

**Water**  
 Standing Water Level  
 Out flow  
 In flow

**Investigation Type**  
 Hand Auger  
 Test Pit

Produced with Core-GS

<b>Contractor:</b> Geocivil	<b>Rig/Plant Used:</b>	<b>Page No.:</b> 23 of 25	<b>Logged By:</b> D.O	<b>Checked By:</b> 	<b>Hole Depth:</b> 2.50 m
--------------------------------	------------------------	------------------------------	--------------------------	------------------------	------------------------------




# SITE PLAN

**Lab Job No:** 8368-008  
**Client:** Opus Whangarei  
**Project:** Bowergate Farms  
**Location:** Ruawai  
**Report No:** W18-013  
**REF:** 8011

**Tested by** D.O/D.M  
**Date:** 10,11,12,16 & 17/01/2018  
**Page:** 24 of 25

*Approximate Test Locations*






# SITE PLAN


**Lab Job No:** 8368-008  
**Client:** Opus Whangarei  
**Project:** Bowergate Farms  
**Location:** Ruawai  
**Report No:** W18-013  
**REF:** 8011

**Tested by** D.O/D.M  
**Date:** 10,11,12,16 & 17/01/2018  
**Page:** 25 of 25


## Approximate Test Locations



**Project:**  
**Location:**



**Project:**  
**Location:**



**Calculation parameters**

Permeability: Based on  $SBT_n$

SPT  $N_{60}$ : Based on  $I_c$  and  $q_t$

Young's modulus: Based on variable alpha using  $I_c$  (Robertson, 2009)


Relative density constant,  $C_{Dr}$ : 350.0

Phi: Based on Kulhawy & Mayne (1990)

● User defined estimation data




**Project:**  
**Location:**



**Calculation parameters**

Constrained modulus: Based on variable  $\alpha$  using  $I_c$  and  $Q_{ln}$  (Robertson, 2009)    OCR factor for clays,  $N_{kt}$ : 0.33  
 Go: Based on variable  $\alpha$  using  $I_c$  (Robertson, 2009)    ● User defined estimation data  
 Undrained shear strength cone factor for clays,  $N_{kt}$ : 14    ● Flat Dilatometer Test data

**Project:**  
**Location:**




**Calculation parameters**


Soil Sensitivity factor,  $N_s$ : 7.00

—●— User defined estimation data

**Project:**  
**Location:**



**Project:**  
**Location:**




**Calculation parameters**

Permeability: Based on  $SBT_n$   
 SPT  $N_{60}$ : Based on  $I_c$  and  $q_t$   
 Young's modulus: Based on variable alpha using  $I_c$  (Robertson, 2009) —●— User defined estimation data  
 Relative density constant,  $C_{Dr}$ : 350.0  
 Phi: Based on Kulhawy & Mayne (1990)




**Project:**  
**Location:**



**Calculation parameters**

Constrained modulus: Based on variable  $\alpha$  using  $I_c$  and  $Q_{in}$  (Robertson, 2009)    OCR factor for clays,  $N_{kt}$ : 0.33  
 Go: Based on variable  $\alpha$  using  $I_c$  (Robertson, 2009)    ● User defined estimation data  
 Undrained shear strength cone factor for clays,  $N_{kt}$ : 14    ● Flat Dilatometer Test data

**Project:**  
**Location:**




**Calculation parameters**


Soil Sensitivity factor,  $N_s$ : 7.00

● User defined estimation data

**Project:**  
**Location:**








**Project:**  
**Location:**



**Calculation parameters**

Permeability: Based on  $SBT_n$   
 SPT  $N_{60}$ : Based on  $I_c$  and  $q_t$   
 Young's modulus: Based on variable alpha using  $I_c$  (Robertson, 2009) —●— User defined estimation data  
 Relative density constant,  $C_{Dr}$ : 350.0  
 Phi: Based on Kulhawy & Mayne (1990)

**Project:**  
**Location:**




**Calculation parameters**

Constrained modulus: Based on variable  $\alpha$  using  $I_c$  and  $Q_{in}$  (Robertson, 2009)  
 Go: Based on variable  $\alpha$  using  $I_c$  (Robertson, 2009)  
 Undrained shear strength cone factor for clays,  $N_{kt}$ : 14  
 OCR factor for clays,  $N_{kt}$ : 0.33  
 —●— User defined estimation data  
 —●— Flat Dilatometer Test data



**Project:**  
**Location:**




**Calculation parameters**


Soil Sensitivity factor,  $N_s$ : 7.00

—●— User defined estimation data

**Project:**  
**Location:**




**Project:**  
**Location:**



**Calculation parameters**

Permeability: Based on  $SBT_n$   
 SPT  $N_{60}$ : Based on  $I_c$  and  $q_t$   
 Young's modulus: Based on variable alpha using  $I_c$  (Robertson, 2009) —●— User defined estimation data  
 Relative density constant,  $C_{Dr}$ : 350.0  
 Phi: Based on Kulhawy & Mayne (1990)


**Project:**  
**Location:**



**Calculation parameters**

Constrained modulus: Based on variable  $\alpha$  using  $I_c$  and  $Q_{in}$  (Robertson, 2009)    OCR factor for clays,  $N_{kt}$ : 0.33  
 Go: Based on variable  $\alpha$  using  $I_c$  (Robertson, 2009)    ● User defined estimation data  
 Undrained shear strength cone factor for clays,  $N_{kt}$ : 14    ● Flat Dilatometer Test data

**Project:**  
**Location:**









**Calculation parameters**

Soil Sensitivity factor,  $N_s$ : 7.00


● User defined estimation data



**Project:**  
**Location:**




**Project:**  
**Location:**



**Calculation parameters**

Permeability: Based on  $SBT_n$   
 SPT  $N_{60}$ : Based on  $I_c$  and  $q_t$   
 Young's modulus: Based on variable alpha using  $I_c$  (Robertson, 2009) —●— User defined estimation data  
 Relative density constant,  $C_{Dr}$ : 350.0  
 Phi: Based on Kulhawy & Mayne (1990)

**Project:**  
**Location:**




**Calculation parameters**

Constrained modulus: Based on variable  $\alpha$  using  $I_c$  and  $Q_{ln}$  (Robertson, 2009)    OCR factor for clays,  $N_{kt}$ : 0.33  
 Go: Based on variable  $\alpha$  using  $I_c$  (Robertson, 2009)    ● User defined estimation data  
 Undrained shear strength cone factor for clays,  $N_{kt}$ : 14    ● Flat Dilatometer Test data

**Project:**

**Location:**








**Calculation parameters**

Soil Sensitivity factor,  $N_s$ : 7.00

● User defined estimation data


**Project:**  
**Location:**



- SBT legend**
- 1. Sensitive fine grained
  - 2. Organic material
  - 3. Clay to silty clay
  - 4. Clayey silt to silty clay
  - 5. Silty sand to sandy silt
  - 6. Clean sand to silty sand
  - 7. Gravely sand to sand
  - 8. Very stiff sand to clayey sand
  - 9. Very stiff fine grained




**Project:**  
**Location:**



**Calculation parameters**

Permeability: Based on  $SBT_n$   
 SPT  $N_{60}$ : Based on  $I_c$  and  $q_t$   
 Young's modulus: Based on variable alpha using  $I_c$  (Robertson, 2009) —●— User defined estimation data  
 Relative density constant,  $C_{Dr}$ : 350.0  
 Phi: Based on Kulhawy & Mayne (1990)


**Project:**  
**Location:**



**Calculation parameters**

Constrained modulus: Based on variable  $\alpha$  using  $I_c$  and  $Q_{in}$  (Robertson, 2009)    OCR factor for clays,  $N_{kt}$ : 0.33  
 Go: Based on variable  $\alpha$  using  $I_c$  (Robertson, 2009)    ● User defined estimation data  
 Undrained shear strength cone factor for clays,  $N_{kt}$ : 14    ● Flat Dilatometer Test data

**Project:**  
**Location:**










**Calculation parameters**

Soil Sensitivity factor,  $N_s$ : 7.00

—●— User defined estimation data

**Project:**  
**Location:**






**Calculation parameters**

Permeability: Based on  $SBT_n$   
 SPT  $N_{60}$ : Based on  $I_c$  and  $q_t$   
 Young's modulus: Based on variable alpha using  $I_c$  (Robertson, 2009) —●— User defined estimation data  
 Relative density constant,  $C_{Dr}$ : 350.0  
 Phi: Based on Kulhawy & Mayne (1990)




**Project:**  
**Location:**



**Calculation parameters**

Constrained modulus: Based on variable  $\alpha$  using  $I_c$  and  $Q_{ln}$  (Robertson, 2009)    OCR factor for clays,  $N_{kt}$ : 0.33  
 Go: Based on variable  $\alpha$  using  $I_c$  (Robertson, 2009)    ● User defined estimation data  
 Undrained shear strength cone factor for clays,  $N_{kt}$ : 14    ● Flat Dilatometer Test data

**Project:**  
**Location:**




**Calculation parameters**


Soil Sensitivity factor,  $N_s$ : 7.00

—●— User defined estimation data



# **Appendix C – Stability Analyses**







**Bowergate Farm**

Static conditions - Short Term - Existing Stop Bank upgrade without ground improvement

<i>Analysis Description</i>	Static conditions - Short Term - Existing Stop Bank upgrade without ground improvement	
<i>Drawn By</i>	SR	<i>Company</i> WSP - Opus International Consultants
<i>Date</i>	02/02/2018, 3:59:23 PM	<i>File Name</i> Static Conditions-Undrained- no GI.slim



Material Name	Color	Unit Weight (kN/m <sup>3</sup> )	Strength Type	Cohesion (kPa)	Phi (deg)	Cohesion Type	Water Surface	Hu Type	Hu	B-Bar	Mat. Weight Cause Excess Pore Pressure	Phi b (deg)	Air Entry (kPa)
Estuarine Alluvium Soils - Soft Clay/Silty Clay ( $\rho_c=0.1-0.3$ MPa)		18	Undrained	10		Constant	Water Surface	Custom	0	0	No	0	0
Stiff Clay & Silty Clay ( $\rho_c=1.2-2.8$ MPa)		20	Undrained	75		Constant	Water Surface	Custom	0	0	No	0	0
Medium Dense/Dense Sand & Silty Sand		20	Undrained	150		Constant	Water Surface	Custom	0	0	No	0	0
Existing Embankment		18	Undrained	70		Constant	Water Surface	Custom	0	0	No	0	0
Rock Filled Berm		20	Mohr-Coulomb	2	38		Water Surface	Custom	0	0	No	0	0
Embankment Top Up		20	Undrained	100		Constant	Water Surface	Custom	0	0	No	0	0

Support Name	Color	Type	Force Application	Material Dependent	Adhesion (kPa)	Friction Angle (deg)	Shear Strength Model	Force Orientation	Anchorage	Strip Coverage (%)	Tensile Strength (kN/m)
Geogrid		Geotextile	Active (Method A)	No	5	20	Linear	Bisector of Parallel and Tangent	Slope Face	100	45



Project



Bowergate Farm

Analysis Description

Static conditions - Short Term - Existing Stop Bank upgrade with ground improvement

Drawn By

SR

Company

WSP - Opus International Consultants



Date

02/02/2018, 3:59:23 PM

File Name

Static Conditions-Undrained- with GI.slim







Material Name	Color	Unit Weight (kN/m <sup>3</sup> )	Strength Type	Cohesion (kPa)	Phi (deg)	Water Surface	Hu Type	Hu	B-Bar	Mat. Weight Causes Excess Pore Pressure	Phi b (deg)	Air Entry (kPa)
Estuarine Alluvium Soils - Soft/Very Soft Clay/Silty Clay (qc=0.1-0.3 MPa)	[Blue]	18	Mohr-Coulomb	0	22	Water Surface	Custom	1			0	0
Stiff Clay & Silty Clay (qc=1.2-2.8 MPa)	[Yellow]	20	Mohr-Coulomb	5	30	Water Surface	Custom	1			0	0
Medium Dense/Dense Sand & Silty Sand	[Grey]	20	Mohr-Coulomb	10	34	Water Surface	Custom	1			0	0
Existing Embankment	[Pink]	18	Mohr-Coulomb	5	30	Water Surface	Custom	1			0	0
Rock Filled Berm	[Red]	20	Mohr-Coulomb	2	38	Water Surface	Custom	1			0	0
Embankment Top up	[Purple]	20	Mohr-Coulomb	7	32	Water Surface	Custom	1			0	0

Support Name	Color	Type	Force Application	Material Dependent	Adhesion (kPa)	Friction Angle (deg)	Shear Strength Model	Force Orientation	Anchorage	Strip Coverage (%)	Tensile Strength (kN/m)
Geogrid	[Purple]	Geotextile	Active (Method A)	No	5	20	Linear	Bisector of Parallel and Tangent	Slope Face	100	45




Project: Bowergate Farm

Analysis Description: Static conditions - Long term - Existing Stop Bank upgrade without ground improvement  
 Drawn By: SR  
 Date: 02/02/2018, 3:59:23 PM  
 Company: WSP - Opus International Consultants  
 File Name: Static Conditions-Drained- without GI.slm





Material Name	Color	Unit Weight (kN/m <sup>3</sup> )	Strength Type	Cohesion (kPa)	Phi (deg)	Water Surface	Hu Type	Hu	B-Bar	Mat. Weight Causes Excess Pore Pressure	Phi b (deg)	Air Entry (kPa)
Estuarine Alluvium Soils - Soft/Very Soft Clay/Silty Clay (qc=0.1-0.3 MPa)		18	Mohr-Coulomb	0	22	Water Surface	Custom	1			0	0
Stiff Clay & Silty Clay (qc=1.2-2.8 MPa)		20	Mohr-Coulomb	5	30	Water Surface	Custom	1			0	0
Medium Dense/Dense Sand & Silty Sand		20	Mohr-Coulomb	10	34	Water Surface	Custom	1			0	0
Existing Embankment		18	Mohr-Coulomb	5	30	Water Surface	Custom	1			0	0
Rock Filled Berm		20	Mohr-Coulomb	2	38	Water Surface	Custom	1			0	0
Embankment Top up		20	Mohr-Coulomb	7	32	Water Surface	Custom	1			0	0

Support Name	Color	Type	Force Application	Material Dependent	Adhesion (kPa)	Friction Angle (deg)	Shear Strength Model	Force Orientation	Anchorage	Strip Coverage (%)	Tensile Strength (kN/m)
Geogrid		Geotextile	Active (Method A)	No	5	20	Linear	Bisector of Parallel and Tangent	Slope Face	100	45



Bowergate Farm

Project		Static conditions - Long term - Existing Stop Bank upgrade with ground improvement	
Analysis Description		WSP - Opus International Consultants	
Drawn By	SR	Scale	1:250
Date	02/02/2018, 3:59:23 PM	Company	WSP - Opus International Consultants
		File Name	Static Conditions-Drained- with GI.slm



Material Name	Color	Unit Weight (kN/m <sup>3</sup> )	Strength Type	Cohesion (kPa)	Phi (deg)	Cohesion Type	Water Surface	Hu Type	Hu
Estuarine Alluvium Soils - Soft/Very Soft Clay-Silty Clay (qc=0.1-0.3 MPa)		18	Undrained	10		Constant	Water Surface	Custom	0
Stiff Clay & Silty Clay (qc=1.2-2.8 MPa)		20	Undrained	75		Constant	Water Surface	Custom	0
Medium Dense/Dense Sand & Silty Sand		20	Undrained	150		Constant	Water Surface	Custom	0
Embankment Fill		18	Undrained	70		Constant	Water Surface	Custom	0



**Bowergate Farm**

Static conditions - Short term - New Stop Bank (without Ground Improvement)

SR      Scale 1:250      Company WSP - Opus International Consultants

02/02/2018, 3:59:23 PM      Date      File Name Static Conditions-Undrained.slim

Project



Material Name	Color	Unit Weight (kN/m <sup>3</sup> )	Strength Type	Cohesion (kPa)	Phi (deg)	Cohesion Type	Water Surface	Hu Type	Hu B-Bar	Mat. Weight Cause Excess Pore Pressure	Phi b (deg)	Air Entry (kPa)
Estuarine Alluvium Soils - Soft/Very Soft Clay-Silty Clay (qc=0.1-0.3 MPa)		18	Undrained	10		Constant	Water Surface	Custom	0	No	0	0
Stiff Clay & Silty Clay (qc=1.2-2.8 MPa)		20	Undrained	75		Constant	Water Surface	Custom	0	No	0	0
Medium Dense/Dense Sand & Silty Sand		20	Undrained	150		Constant	Water Surface	Custom	0	No	0	0
Embankment Fill		18	Undrained	70		Constant	Water Surface	Custom	0	No	0	0
Rock Filled Berm		20	Mohr-Coulomb	2	38		Water Surface	Custom	1	No	0	0

Support Name	Color	Type	Force Application	Material Dependent	Adhesion (kPa)	Friction Angle (deg)	Shear Strength Model	Force Orientation	Anchorage	Strip Coverage (%)	Tensile Strength (kN/m)
Geogrid		GeoTextile	Active (Method A)	No	5	20	Linear	Bisector of Parallel and Slope Face tangent		100	45



**Bowergate Farm**

Static conditions - Short term - New Stop Bank with ground improvement

Project

---

Analysis Description

Static conditions - Short term - New Stop Bank with ground improvement

Company

---

Drawn By

SR

Company

---

Date

02/02/2018, 3:59:23 PM

Company

---



Scale 1:250

Company

---


Static Conditions-Undrained- with GI trial.slm

File Name



Material Name	Color	Unit Weight (kN/m <sup>3</sup> )	Strength Type	Cohesion (kPa)	Phi (deg)	Water Surface	Ru
Estuarine Alluvium Soils - Soft/Very Soft Clay-Silty Clay (qc=0.1-0.3 MPa)		18	Mohr-Coulomb	0	22	Water Surface	
Stiff Clay & Silty Clay (qc=1.2-2.8 MPa)		20	Mohr-Coulomb	5	30	Water Surface	
Medium Dense/Dense Sand & Silty Sand		20	Mohr-Coulomb	10	34	Water Surface	
Embankment Fill		18	Mohr-Coulomb	5	35	Water Surface	





**Project**  
Bowergate Farm

---

*Analysis Description*  
Static conditions - Short term - New Stop Bank (without Ground Improvement)

*Company*  
WSP-Opus International Consultants

---

*Drawn By*  
SR



*Scale*  
1:250

*File Name*  
Static-Drained-no GI.slim

---

*Date*  
02/02/2018, 3:59:23 PM





Material Name	Color	Unit Weight (kN/m <sup>3</sup> )	Strength Type	Cohesion (kPa)	Phi (deg)	Cohesion Type	Water Surface	Hu Type	Hu	B-Bar	Mat. Weight Causes Excess Pore Pressure	Phi b (deg)	Air Entry (kPa)
Estuarine Alluvium Soils - Soft/Very Soft Clay-Silty Clay (c=0.1-0.3 MPa)	Blue	18	Mohr-Coulomb	0	22		Water Surface	Custom	1	0	No	0	0
Stiff Clay & Silty Clay (c=1.2-2.8 MPa)	Yellow	20	Mohr-Coulomb	5	30		Water Surface	Custom	1	0	No	0	0
Medium Dense/Dense Sand & Silty Sand	Grey	20	Mohr-Coulomb	10	34		Water Surface	Custom	1	0	No	0	0
Embankment Fill	Pink	18	Mohr-Coulomb	5	35		Water Surface	Custom	1	0	No	0	0
Material 6	Red	20	Mohr-Coulomb	1	35		Water Surface	Custom	1	0	No	0	0

Support Name	Color	Type	Force Application	Material Dependent	Adhesion (kPa)	Friction Angle (deg)	Shear Strength Model	Force Orientation	Anchorage	Strip Coverage (%)	Tensile Strength (kN/m)
Geogrid	Blue	GeoTextile	Active (Method A)	No	5	20	Linear	Bisector of Parallel and Tangent	Slope Face	100	45

Project



Bowergate Farm

Analysis Description

Static conditions - Long term - New Stop Bank with ground improvement

Drawn By

SR

Scale

1:200

Company

WSP - Opus International Consultants

Date

02/02/2018, 3:59:23 PM


File Name

Static Conditions-drained- with GI.slim



# **Appendix D – Schemes of Options**

Figure 5 - Existing Stop Bank Upgrade



**Notes:**

Design shall take into consideration the source material for filling and ground improvements. Preference for clay fill shall for low density to minimize load on the existing ground


Permeability of source material for ground improvement layer shall be checked and stabilized if required

Design shall consider construction sequencing and site access.

The existing ground is extremely sensitive and care shall be taken to minimize ground disturbance during construction.

Involvement of the a Contractor during detailed design would be prudent to minimise the construction risk for KDC

Figure 6 - New Stop Bank Construction



**Notes:**

Design shall take into consideration the source material for filling and ground improvements. Preference for Permeability of source material for ground improvement layer shall be checked and stabilized if required Design shall consider construction sequencing and site access.

The existing ground is extremely sensitive and care shall be taken to minimize ground disturbance during construction of the a Contractor during detailed design would be prudent to minimise the construction risk for

ddmmyy in full

Name

Address

Address

**Address and postcode**

Dear name

### **Raupo Stopbank Reinstatement**

This letter is seeking your feedback on a stopbank issue that requires resolution. The situation has resulted in the Drainage Committee and Council having a different view to the directly affected landowners. We have resolved that a key input into making the final decision will be feedback from the affected community, being Ruawai.

### **Background**

The Raupo drainage scheme is overseen by a committee of locals; Ian Beattie (Chair), David Hart, Brian Madsen, Ross McKinley, Ken Whitehead, Greg Gent, Councillor Anna Curnow and Mayor Dr Jason Smith.

The Committee works with Council Engineers, on a voluntary basis, to keep our drainage scheme operating at the level it does. This structure has been in place for many years. Landowners collectively in the district pay a targeted rate of \$349,000 annually which is solely used for the maintenance and capital works associated with drainage. The Committee has a modest contingency fund which is there for unforeseen expenses.

The capital works programme both recently and into the future is dominated by floodgate renewals as all floodgates are at a similar age and are showing signs of potential failure. Each renewal costs around \$120,000 to replace.

A past owner of the land under consideration removed a portion of the stopbank and constructed a new bank that encircled a part of their property that had sat outside of the stopbank and therefore the drainage district. We can find no evidence that this activity had formal approval. The farm has since sold.

### **Current situation**

An engineer's report has identified that the section of stopbank (as identified above) that was moved is far below the standard needed to provide adequate flood protection of Ruawai. The Committee has now



put a "peg in the sand" and prefers the agreed solution to be implemented. The risk to Ruawai is simply too great for this matter to be left to continue.

### **Cost implications**

There are two options to remedy this:

- Option 1 – Reinstatement of the stopbank to its original condition and position. The cost of this to be around \$750,000.
- Option 2 – Improve the stopbank that was created by the landowner that reclaimed the land. That will cost in the vicinity of \$1,600,000.

Reinstating the original stopbank would mean Council would cease collecting land drainage rates on 19.8 hectares of land which would then sit outside of the Raupo Drainage District. This land would have limited flood protection from the existing (moved) stopbank which we are not suggesting we would dismantle and would be the landowner's responsibility from thereon.

### **Committee's and Council's preferred option**

Option 1: To reinstate the historic stopbank at an approximate cost of \$750,000 to all Raupo Drainage District ratepayers. This is the most cost-effective option, it does not set a precedent (there is other Ruawai land outside of the main stopbank) and restores an appropriate level of flood protection, this would see an increase in the Raupo Drainage targeted rate of between 15% - 21% per annum over 20 years.

The rates impact of option 2, would see an increase in the Raupo drainage rate of 34% - 45% per annum over 20 years.

As part of informing the final decision, we are encouraging you to let us know your views. This can be done by contacting myself, a Committee member, by email to [council@kaipara.govt.nz](mailto:council@kaipara.govt.nz) or by telephone to Shelley Paniora on 09 439 3225 before 4.00pm Friday 20 October 2017.

Yours faithfully

Curt Martin  
**Acting Chief Executive**

## **Closure**

**Kaipara District Council  
Dargaville**