



# Mangawhai CWWTP

Stage 1 Summary Report

Contact Details

Name: *Jessica Moser*

Opus House, Princes Street  
Private Bag 3057, Waikato Mail Centre, Hamilton  
3240  
New Zealand

Telephone: +64 7 838 9344  
Mobile: 027 541 0573

Document Details:

Date: 10/09/2018  
Reference: 1-13586.00  
Status: Final

Prepared By



---

Jessica Moser  
Graduate Environmental Engineer

Reviewed By



---

Andrew Springer  
Principal Wastewater Treatment Engineer

Approved for Release By



---

Eros Foschieri  
Team Leader – 3 Waters

## Contents

1	Executive Summary.....	1
2	Issues, Root Causes and Effects .....	1
3	Risks.....	1
4	Prioritisation.....	2
5	Conclusion.....	2
	Appendix A: Minutes of Root Cause Workshop.....	3
	<i>Appendix 1: Issues with the WWTP</i>	
	<i>Appendix 2: Priority of Issues</i>	
	<i>Appendix 3: Possible Solutions</i>	
	<i>Appendix 4: Workshop Slides</i>	

## 1 Executive Summary

As outlined in the Offer of Service for Upgrade of Mangawhai WWTP, 20 June 2018, the technical support that WSP Opus will provide shall be broken into four stages; including Needs Assessment, Develop Solutions, Procurement and Delivery. This approach is based on determining the root cause of existing and future issues and understanding the associated risk in order to prioritise the required upgrades. This report summarises the findings of the Needs Assessment for the upgrade of Mangawhai WWTP and presents the finalised issues, risks and prioritisation. The assessment included an inspection of the plant, review of the influent and effluent data and a Root Cause Workshop. The minutes of meeting from the workshop have been included in Appendix A and provide the basis for this summary report.

## 2 Issues, Root Causes and Effects

The strategy for identifying the needs of the plant, included evaluating the existing performance data and inspection of the site. In this way, all the information on the existing condition of the plant and its performance could be assessed. To ensure that no issues would be missed, the assessment was conducted in the form of a workshop where all stakeholders could contribute to the identification of issues.

The issues were captured during the workshop held on 31<sup>st</sup> August and each issue was evaluated for its root cause and its potential effects. The results from the workshop are included in **Appendix 1** of the Minutes of Meeting (**Appendix A**).

## 3 Risks

The method for prioritisation of the identified issues involved evaluating each issue for its associated likelihood and impact. The key for each ranking is included in **Appendix 2** of the Minutes of Meeting. The table below summarises the risk rating for each issue as was agreed upon during the workshop.

Table 1. Risk Rating for Identified Issues

		Impact (I)				
		VL	L	M	H	VH
Likelihood (L)	VH			2, 10, 11		
	H			4, 13	9, 14	5, 6, 12
	M					
	L			7		
	VL					

## 4 Prioritisation

The issues have been listed below in their order of prioritisation from most important to least important as determined by the associated risk of each issue. The issues are labelled according to the number that each issue was recorded under during the Root Cause Workshop.

- 5 The decanter drives are wearing out and there is a long lead time for these to be replaced. This means that in the event of a drive wearing out, the process would be restricted to one tank for approximately 6 weeks or more while waiting for the replacement drive to arrive to site. The quality of the effluent would be compromised during the time that the plant would run on one tank.
- 6 The capacity of the existing aeration system is insufficient for consistently meeting the DO setpoint. This issue will continue to get worse as the population in the catchment increases.
- 12 The existing blowers sometimes run at peak demand. The forecasted continued growth in the catchment will increase the demand on the blowers and result in prolonged periods of peak demand and there is currently no standby blower provided.
- 9 The odour motor cover has corroded and left the moving machinery unguarded which is a serious safety concern.
- 14 There has been an increase in flow from the pump station TPS which has resulted in more flow being pumped to the WWTP. This increase exceeds the screen capacity and may also exceed the intermediate pump and transfer pump capacity and result in overspill of effluent.
- 2 Seasonal settlement problems have been leading to solids loss from the reactor.
- 10 There have been TDS exceedances recorded in some samples.
- 11 There is no RAS flow meter and therefore no method to control RAS flow rates if required.
- 4 There is no control of aeration in the anoxic zone. There is a need to both prevent solids build up in the tank and also establish anoxic conditions for nitrate removal.
- 13 High flow mode leads to short cycle and poor treatment. These incidences will increase in frequency with the expected 35% growth over the next ten years.
- 7 There is settlement occurring in the intermediate tank.

## 5 Conclusion

The needs assessment (Stage 1) has been completed and has resulted in the definition and prioritisation of existing issues with the Mangawhai WWTP as well as issues that are expected to occur within the next 10 years. The next stage of this project is to develop solutions that will meet these needs. The developed solutions will form the basis for supplier enquiry.

## Appendix A: Minutes of Root Cause Workshop

## Minutes of Meeting

---

<b>File No:</b>	1-13586.00	<b>Date:</b>	31/08/2018	<b>Time:</b>	11am-3pm
<b>Subject:</b>	Mangawhai CWWTP				
<b>Location:</b>	KDC Office, Mangawhai	<b>Minutes by:</b>	Jessica Moser		

---

	Persons Present	Organisation
1	Brian Armstrong, BA	Kaipara District Council
2	Donnick Mugutso, DM	Kaipara District Council
3	Mark Bell, MB	Kaipara District Council
4	Robin Johnson, RJ	Trility
5	David Ollerton, DO	Trility
6	Andrew Springer, AS	WSP Opus
7	Eros Foschieri, EF	WSP Opus
8	Jessica Moser, JM	WSP Opus

---

Item	Discussion and Action
------	-----------------------

---

1	<p><b>Overview</b></p>
---	------------------------

AS presented an overview of the Mangawhai CWWTP which included site layout, flow, performance and growth forecast.

2	<p><b>Issues with the WWTP</b></p>
---	------------------------------------

AS went through each step of the plant methodically to capture the existing issues. The issues were discussed and agreed upon by all present. A summary of the issues which were collated are included in **Appendix 1**.

3	<p><b>Root Cause of the Issues</b></p>
---	--

For each issue identified, the group discussed what the root cause for that issue might be as well as the effect of that issue at present and/or in the future (up to 10 years). These causes & effects were agreed upon by all present and listed in **Appendix 1**.

4	<p><b>Priority of Issues</b></p>
---	----------------------------------

Each issue was ranked according to likelihood and impact, a table for each of these factors is included in **Appendix 2** to detail the meaning for each score. The combination of each issues likelihood and impact scores determined where it sits on the risk table. The completed risk table is included in **Appendix 2** and was agreed upon by all present. The risk table was used to prioritise the issues in terms of which should be resolved first, the order of priority is included in **Appendix 2**.

5	<p><b>Possible Solutions</b></p>
---	----------------------------------

Potential solutions were briefly discussed by all present and suggestions are included in **Appendix 3**. The options for solutions will be confirmed at Stage 2 of the project.

<b>Item</b>	<b>Discussion and Action</b>		
6	Confirm site boundary limits <b>Completed</b>	MB	7/9/18
7	Confirm pressure of air in main at blower at bottom water level as indicator of change in diffuser performance	RJ	14/9/18
8	Assess sand filter condition and sand quantity by inspection	RJ	14/9/18
9	Replace cover on odour motor	RJ	ASAP
10	Issue workshop report for comment <b>Completed</b>	AS	7/9/18
11	Electrical and structural condition assessment by Trility next year.	DO	2019
12	Provide estimate of hours for Stage 2	AS, JM	20/9/18
13	Work up options then have a workshop to agree preferred options	AS, JM	12/10/18
14	Propose procurement strategy	ALL	19/10/18
15	Price options with Trility.	DO, AS	26/10/18
16	Specifications to be produced as needed	AS, JM	TBC
17	Complete specified work	TBC	TBC
<b>After meeting correspondence</b>			
18	DM in discussion with Curt Martin (KDC) raised another potential issue that may need addressing. The issue relates to the possibility of overflows at the inlet works due to increased peak flows to the treatment plant. Further data analysis is required to understand duration of high flows currently and impact on wet well level at TPS. Growth strategy required for catchment upgrades to predict when increase in flow may occur.		



## Appendix 1: Issues with the WWTP

	Likelihood	Impact
1. Removed from notes as was combined in 4 below.	-	-
2. <b>Issue:</b> Seasonal settlement problems leading to solids loss from reactor <b>Cause:</b> Floc loading & variable feed, limited control on RAS, intermediate not buffering adequately <b>Effect:</b> Impact on TSS, especially during high flows, but limited by sand filters	VH	M
3. <b>Issue:</b> Inaccessible coarse air valve <b>Cause:</b> Valve installed outside handrail <b>Effect:</b> Safety is managed by not using the valve	-	-
4. <b>Issue:</b> No control of aeration in anoxic zone, need to prevent solids build up in tank, but want anoxic condition to remove nitrate. <b>Cause:</b> Inaccessible manual valve installed outside handrail <b>Effect:</b> Safety RISK is managed by not using the valve	H	M
5. <b>Issue:</b> Decanter drives wearing out. Long lead time item that will impact on performance of effluent as restricted to one tank only. <b>Cause:</b> 10 years old & running 2 tanks at once <b>Effect:</b> Would take ≥6 weeks to replace	H	VH
6. <b>Issue:</b> Aeration capacity not meeting DO set point at times. Predictions indicate will get worse with growth. <b>Cause:</b> Design point exceeded due to growth <b>Effect:</b> Compliance, particularly ammonia and TN	H	VH
7. <b>Issue:</b> Settlement in intermediate tank <b>Cause:</b> Solids settle in flat bottom tank below level of pumps, insufficient scour normally <b>Effect:</b> Manually managed (cleaning 3x per year)	L	M
8. <b>Issue:</b> Media in sand filters unknown <b>Cause:</b> Has not been inspected since commissioning <b>Effect:</b> Not a compliance issue currently	?	?
9. <b>Issue:</b> Motor cover corroded <b>Cause:</b> Some H <sub>2</sub> S leakage at odour control <b>Effect:</b> Serious risk of Harm	H	H
10. <b>Issue:</b> TDS exceedance of average standard in some samples <b>Cause:</b> More concentrated wastewater in summer <b>Effect:</b> Not within our reasonable control	VH	M
11. <b>Issue:</b> No RAS flow meter so unable to control RAS flow rates if required <b>Cause:</b> Not included in design <b>Effect:</b> No control of RAS may impact on denitrification and sludge settlement	VH	M
12. <b>Issue:</b> Blowers at peak demand at times. Growth will increase demand and require longer operation in this condition. No standby provided. <b>Cause:</b> Increase due to load growth, <b>Effect:</b> Possible blower failure will lead to non-compliance	H	VH

- |   |   |   |
|---|---|---|
| 13. <b>Issue:</b> High flow mode leads to short cycle and poor treatment. Will increase in frequency with expected 35% growth over 10 years.<br><b>Cause:</b> Increase flow exceeds threshold for high flow mode operation<br><b>Effect:</b> Resulting in short cycles at times of high summer loading.   | H | M |
| 14. <b>Issue:</b> Increase in flow at TPS requires more flow to be pumped to WWTP. Increase exceeds screen capacity and may exceed intermediate pump and transfer pump capacity. Current peak daily flow at 1600 m <sup>3</sup> /d, but instant flow at 5500 m <sup>3</sup> equivalent.<br><b>Cause:</b> Increase in flow from catchment growth at peak times.<br><b>Effect:</b> Resulting in higher instantaneous flows to treatment, potentially overloading systems and may result in overspill of effluent. | H | H |

## Appendix 2: Priority of Issues

### Key for Likelihood Ranking

	<b>Time</b>	<b>Descriptive</b>	<b>Frequency</b>
<b>VH</b>	< 1 Year	Almost Certain	Nearly Continuous
<b>H</b>	1-5 Year	Likely	Common
<b>M</b>	5-10 Year	Probable	Occasional
<b>L</b>	10-20 Year	Unlikely	Infrequent
<b>VL</b>	>20 year	Rare	Rare

Key for Impact Ranking

	IMPACT				
	VL	L	M	H	VH
<b>Safety</b>	Injury not needing medical treatment	Injury Needing Medical Treatment, No lost time	Injury Off Work < 5 Days	Permanent Injury, Off Work > 5 Days, Health Issue	Fatality, Permanent Disability
<b>Pollution</b>	Event with potential occurs, but No impact	Cat 4, Local Impact, short duration, include discharge to ground	Cat 3 Short duration Impact, local effect only. Visual Impact	Cat 2 Substantial Impact- including downstream water extraction and use	Cat 1 Fish Kill, impact on downstream water extraction and use
<b>Consent Compliance</b>	No Impact	Sample Exceeds Operational Action Limit	Sample exceeds annual average	Sample Exceeds 90%ile	Consent Condition or Standard Breached
<b>Customer/Community Nuisance</b>	Occasional Nuisance, no complaints	Regular Nuisance, single property	Regular Affecting multiple customers	Widespread Nuisance Local Action Group	Enforcement Action
<b>PR</b>	No Impact	Local Complaint	Social Media Coverage	Local Media Coverage	National media Coverage
<b>Microbial Impact on Water Use</b>	No Impact	Recreational standard of 260 E coli/100ml exceeded < 1 day	Recreational Standard exceeded 1-2 days, can be managed	Recreational Standard Exceeded > 3 days, temporary food restriction	Long term unfit for recreation, food source contamination
<b>Impact on Water Source</b>	No Impact		Irrigation restricted	Water supply restricted take or additional treatment required	Water Supply shut down > 1 day
<b>Irrigation Impacts</b>	No Impact		Exceedance requires storage and Blending	Exceedance of Short term loading rates, within annual average	Pollution impacting on water supply/ exceed annual loading

Risk Table

		Impact (I)				
		VL	L	M	H	VH
Likelihood (L)	VH			2, 10, 11		
	H			4, 13	9, 14	5, 6, 12
	M					
	L			7		
	VL					

Order of priority: 5, 6, 12, 9, 14, 2, 10, 11, 4, 13, 7

## Appendix 3: Possible Solutions

A short review to identify potentially simple solutions was undertaken. The following will be considered in options. Other options may be considered.

2 & 11 RAS Flow Meter and RAS control to zone linked to SCADA

3 & 4 Automate valves to anoxic and move within reach

5 Buy spare drive as shelf spare

**Post Meeting Note:** RJ is seeking pricing for decanter drive spare and will feedback to group once quote and lead time is known

6 & 12 Aeration design to be reviewed and upgraded/ flow balancing

7 Air mix or drain

8 Assess condition of sand filters. Remediate as needed

**Post Meeting Note:** Trility will undertake this inspection and report back on the condition by the end of September

9 Replace cover for motor ASAP

**Post Meeting Note:** The area has been barricaded off and the new cover has been ordered as well as an additional spare. To be installed as soon as delivery to site is achieved.

10 Do nothing- reverse osmosis not viable cost


13 Balance tank/ screen upgrade or TPS storage

## Appendix 4: Workshop Slides



- Overview of Site
- Flows & Performance
- Growth
- Issues
- Root Cause of Issues
- Risk
- Prioritisation
- Next Steps

**What we are doing today**





## Flow Consent Conditions

**Untreated Wastewater Quantity**

- 1 Prior to being discharged to land, all wastewater shall be treated within a wastewater treatment plant located on Lot 1 DP 153155 PT Lot 3 DP 108638 Allot 389 Mangawhai Psh Bk II Mangawhai SD SUBJ TO EASE-RES, at or about location co-ordinates 1743192E 6005357N.  
  
This wastewater treatment plant shall include a granular filtration system and disinfection system. The granular filtration system shall be designed to remove helminths. For the purpose of these consents, disinfection is defined as the use of a process designed specifically to reduce the number of viable, potentially infectious, micro-organisms in the wastewater.
- 2 The quantity of wastewater received at the treatment plant shall not exceed 5,500 cubic metres in any 24 hour period, as measured between 9.00 a.m. on one day and 9.00 a.m. on the following day. For compliance purposes, this condition shall be monitored in accordance with Schedule 1 (attached).
- 3 A meter with accuracy of  $\pm 5\%$  shall be installed and maintained on the inlet to the wastewater treatment plant. The meter shall be used to measure the volume of wastewater entering the wastewater treatment plant. To determine the level of accuracy of the influent flow meter, the meter shall be calibrated at regular intervals in accordance with Schedule 1 (attached).

wsp | OPUS






## Inflow Statistics

Increase	Year	Qavg (All Year)	Qavg (Autumn/Winter)	Qavg (Spring/Summer)	Qavg (Xmas)	Qmax (All Year)	Qmax (Xmas)
		(m <sup>3</sup> /d)					
	2012	301	306	275	598	894	925
	2013	296	262	293	664	971	971
11%	2014	332	297	329	681	1300	1024
6%	2015	354	318	420	701	1024	1142
28%	2016	492	465	473	737	1546	1204
	Total average 2013-2016	368	336	379	696	1210	1085
	L/s	4.265	3.883	4.381	8.053		

WSP | OPUS



## Influent Flow Data



WSP | OPUS

## Concentration of Inlet

Season/year	Average Values (mg/l)						
	TSS	BOD5	Total P	Total N	NH3-N	NO3-N	COO
<b>2013</b>							
Autumn/Winter	505	282	12	84	79	0.04	795
Spring/Summer	362	245	12	89	83	0.03	588
Xmas	401	469	15	109	101	0.05	906
All year	443	287	12	88	82	0.04	735
<b>2014</b>							
Autumn/Winter	362	213	14	84	73	0.02	657
Spring/Summer	333	412	11	62	51	0.03	333
Xmas	460	421	14	128	109	-	939
All year	364	363	11	82	71	0.03	564
<b>2015</b>							
Autumn/Winter	390	299	12	99	78	0.07	765
Spring/Summer	413	336	13	102	82	0.05	696
Xmas	444	417	14	128	110	-	966
All year	421	311	12	97	78	0.07	795
<b>2016</b>							
Autumn/Winter	569	333	12	80	60	0.08	938
Spring/Summer		418	12	84	68	0.10	917
Xmas	605	744	14	109	84	0.06	969
All year	568	371	12	81	64	0.08	929
<b>Total average</b>							
Autumn/Winter	457	282	12	87	72	0.05	789
Spring/Summer	277	353	12	84	71	0.05	634
Xmas	477	513	14	119	101	0.08	943
All year	449	331	12	82	74	0.05	752
	90%ile Values (mg/l)						
Season/year	TSS	BOD5	Total P	Total N	NH3-N	NO3-N	COO
<b>Total average</b>	667.2	446.5	14.62	108.8	96.8	0.1	1054

**Notes:**

A autumn / winter period includes sampling taken from March to August

B spring / summer period includes sampling taken from September to November and February

C Christmas / New Year period includes sampling taken from December and January of the following year.

wsp | OPUS


## Plant Design

Parameter	Design Average*	Peak Week	Current Average	Current Peak	2023 Peak	2028 Peak
Average Flow m <sup>3</sup> /d	600	2120	600	1200	1410	1620
BOD kg/d	180	636	210	840	990	1130
TSS kg/d	180	636	270	572	672	772
TKN kg/d	30	106	105	140	164	188
TP kg/d	7.2	25.4	7.2	13	16	19

\*Based on EcoCare Design Report (2009)

wsp | OPUS

## Timeline of growth



## Consent Conditions

Colour Code Key:

Average Exceeded
Single Sample Exceeded
No Issues

Parameter	Units	Performance Requirements		
		Median	Average	90 <sup>th</sup> Percentile
<b>Group A Parameters (Weekly Sampling)</b>				
E. coli	MPN	10		100
<b>Group B Parameters (15 day Sampling)</b>				
Total Dissolved Solids	mg/L		500	
Total Nitrogen	mg/L		30	
Phosphorus	mg/L		15	
Total Suspended Solids	mg/L		10	
Carbonaceous Biochemical Oxygen Demand	mg/L		10	

Date	E coli point A/B		
	Sample	Method(2)	90%ile
	MPN/100	MPN/100	MPN/100
Tuesday, 4 July 2017	1	1	1
Monday, 10 July 2017	1	1	1
Wednesday, 20 July 2017	1	1	1
Monday, 31 July 2017	1	1	1
Thursday, 10 August 2017	1	1	1
Thursday, 14 August 2017	1	1	1
Monday, 21 August 2017	1	1	1
Thursday, 24 August 2017	1	1	1
Monday, 4 September 2017	1	1	1
Wednesday, 13 September 2017	1	1	1
Monday, 18 September 2017	1	1	1
Monday, 25 September 2017	1	1	1
Monday, 8 October 2017	1	1	1
Monday, 16 October 2017	1	1	1
Tuesday, 24 October 2017	1	1	1
Monday, 30 October 2017	1	1	1
Wednesday, 8 November 2017	1	1	1
Tuesday, 14 November 2017	1	1	1
Thursday, 21 November 2017	1	1	1
Wednesday, 7 December 2017	1	1	1
Monday, 11 December 2017	1	1	1
Thursday, 14 December 2017	1	1	1
Thursday, 28 December 2017	1	1	1

## Effluent Performance Data

wsp OPUS

Date	E coli point A/B		
	Sample	Method(2)	90%ile
	MPN/100	MPN/100	MPN/100
Monday, 9 January 2018	3	1	1
Monday, 22 January 2018	1	1	1
Tuesday, 30 January 2018	1	1	1
Monday, 5 February 2018	1	1	1
Monday, 12 February 2018	1	1	1
Monday, 19 February 2018	1	1	1
Tuesday, 27 February 2018	1	1	1
Monday, 5 March 2018	1	1	1
Tuesday, 13 March 2018	1	1	1
Tuesday, 20 March 2018	1	1	1
Tuesday, 16 April 2018	1	1	1
Wednesday, 14 April 2018	60	1	2.0
Monday, 23 April 2018	1	1	2.0
Monday, 29 April 2018	1	1	1
Thursday, 3 May 2018	1	1	1
Monday, 7 May 2018	1	1	1
Monday, 14 May 2018	1	1	1
Monday, 21 May 2018	1	1	1
Monday, 28 May 2018	1	1	1
Tuesday, 5 June 2018	1	1	1
Monday, 11 June 2018	1	1	1
Tuesday, 19 June 2018	5	1	4.2
Monday, 25 June 2018	1	1	2.0

## Effluent Performance Data

wsp OPUS

## Effluent Performance Data

Month and Day (Month/Day) Date/Time and Location	TSS		TSS		TSS		TP		TP	
	Max. mg/L	Average mg/L	Max. mg/L	Average mg/L	Max. mg/L	Average mg/L	Max. mg/L	Average mg/L	Max. mg/L	Average mg/L
Receptor Discharge Limit										
Monday, 01 Aug 2015	200	870	40	8.2	17.2	47.5	4.5	4.5	4.5	4.2
Wednesday, 03 Aug 2015	200	260	16.0	6.8	14.8	18.8	2.4	2.7	4.5	4.5
Thursday, 04 August 2015	200	240	3.6	7.8	14.8	22.4	2.2	2.2	3.6	4.5
Friday, 07 August 2015	401	288	40	7.2	2.4	15.4	1.5	3.8	4.5	4.8
Monday, 08 September 2015	262	200	20	6.2	6.8	11.4	2.7	2.8	2.8	4.4
Monday, 14 September 2015	400	288	7.6	4.3	8.2	11.2	4.3	3.4	4.6	4.7
Monday, 14 October 2015	400	400	11.8	8.8	14.1	18.2	7.2	4.8	7.2	4.8
Monday, 24 October 2015	402	250	12.8	7.2	20.4	11.4	6.2	6.2	14.8	6.2
Wednesday, 04 November 2015	401	300	4.8	6.3	2.8	12.2	6.8	6.2	7.2	6.8
Thursday, 05 November 2015	402	300	4.6	7.8	14.2	11.4	7.1	6.8	6.6	6.7
Wednesday, 10 December 2015	400	410	3.6	6.2	10.4	12.1	4.2	2.8	4.6	7.2
Wednesday, 23 December 2015	407	400	6.2	7.7	18.8	12.2	16.4	2.8	4.2	7.8
Friday, 15 January 2014	300	400	4.6	6.8	11.4	12.8	6.8	2.1	4.6	7.8
Friday, 19 January 2014	300	400	3.6	4.0	14.8	12.8	6.6	7.8	4.6	5.7
Thursday, 27 February 2014	300	400	11.8	6.8	44.8	12.8	6.8	2.8	4.2	3.6
Monday, 03 February 2014	250	400	10	6.2	14.2	20.8	1.4	6.8	4.2	4.7
Monday, 03 March 2014	300	400	2.6	6.8	17.8	12.1	4.2	6.2	2.6	4.6
Thursday, 06 March 2014	400	400	2.6	6.7	17.8	12.8	6.1	6.8	7.2	6.8
Wednesday, 04 April 2014	407	400	16.8	7.7	14.0	18.8	2.7	4.2	4.8	6.8
Thursday, 04 April 2014	404	400	2.2	7.8	16.1	18.1	7.1	6.2	6.2	6.8
Friday, 11 April 2014	401	400	4.6	6.8	19.8	12.8	6.2	6.6	4.6	7.8
Friday, 18 May 2014	402	404	3.6	6.8	20.0	24.0	2.2	6.1	3.6	4.6
Monday, 23 June 2014	400	400	10.2	7.8	12.8	14.8	6.8	4.8	4.2	4.7
Monday, 01 Aug 2014	400	407	10.4	6.7	17.8	14.8	7.8	4.2	7.8	4.7

wsp | OPUS

## Process Unit Hydraulic Capacity

Description	Estimated Hydraulic Capacity (G/s)
Screen	70
Splitter Box	160 (72 resistors remaining flow)
CASE Decanter System	200 (4 for cyclic discharge in flow)
RAV pump	6.6
WAS pump	14
Intermittent Transfer Pump	40
Filteration System	20
LUV system	22*
Ball Press System	4.10

wsp | OPUS

**WSP | OPUS**

[www.wsp-opus.co.nz](http://www.wsp-opus.co.nz)